

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,

Wichita, Kansas


21-34-43W

Company PANHANDLE EASTERN PIPE LINE
Farm- Interstate No. 04

SEC. 21 T. 34 R. 43W
C SW NW

Total Depth. 4270'
Comm. 6-11-56 Comp. 6-27-56
Shot or Treated.
Contractor. Nye & Snell Drlg. Co.
Issued. 1-12-57

County Morton
KANSAS



Elevation. 3470.35

Production. State Test 401 BOPD

CASING:

10 3/4" 104' w/125 sx cem. 2" tbg. 4154'
7" 1140' w/500 sx cem.
4 1/2" 4248' w/300 sx cem.

Figures indicate Bottom of Formations.

sand-red bed	104
red bed	158
red bed-lime	715
red bed-shale-lime	1125
anhydrite	1160
red bed-shale-sand	1520
shale-sand	1896
shale-shells	2075
shale-shells-sand	2235
sand-shale	2345
shale	2525
lime-shale	3395
sand-lime-shale	3460
lime-shale	3582
lime-shale-sand	3775
lime-shale	4130
shale-sand	4270
Total Depth	

TOPS:

Wabaunsee	2458
Topeka	2654
C.S.O. Lansing	2891
Lansing	3092
Cherokee	3821
Morrow	4078
Purdy sand	4121

PERFORATIONS

4140-4160

Well not treated.