

21-34-43W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock,                      Wichita, Kansas

Company- PANHANDLE EASTERN PIPELINE CO.  
Farm- Interstate                      No. 09

SEC. 21      T. 34      R. 43W  
         C NW NE

Total Depth. 4240'  
Comm. 10-31-56                      Comp. 11-14-56  
Shot or Treated.  
Contractor. Nye & Snell Drlg. Co.  
Issued. 2-2-57

County Morton  
                 KANSAS



CASING:

10 3/4" 101' w/100 sx cem.      2 3/8" tbg & rods 4140'  
7" 1129' w/700 sx cem.  
4 1/2" 4199' w/125 sx cem.

Elevation. 3474.14

Production. State Test 12 BOPH

Figures indicate Bottom of Formations.

sand gravel red bed 105  
red bed 620  
red bed-shale 935  
red bed shale-anhydrite 1134  
shale shells 1375  
shale 1800  
shale-shells 1985  
shale 2190  
shale-lime 3951  
lime 3990  
lime-shale 4090  
lime shale-sand 4230  
lime shale-sand 4240  
Total Depth

TOPS:

Wabaunsee 2468  
Topeka 2670  
CSO Lansing 2909  
Lansing 3109  
Cherokee 3799  
Morrow 4098  
Purdy 4140

Perf. 4142-4150

Well Treatment record;  
Treated 2500 gals.