

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas


21-34-43W

Company- PANHANDLE EASTERN PIPE LINE
Farm- Interstate No. 011

SEC. 21 T. 34 R. 43W
C SW NE
1980' S NL 3300' E WL NE

County Morton
KANSAS

Total Depth. 4260'
Comm. 12-19-56 Comp. 1-5-57
Shot or Treated.
Contractor. Nye & Snell Drlg. Co.
Issued. 3-2-57



Elevation. 3461.74'

Production. Dry

CASING:

10 3/4" 99' w/100 sx cem.
7" 1134' w/750 sx cem.
4 1/2" 4215' w/200 sx cem.

Figures indicate Bottom of Formations.

sand-gravel-red bed 105
red bed 450
red bed-shells 810
red bed-shale-anhydrite 1139
shale-shells-anhydrite 1278
shale-shells 2190
shale-lime 3928
lime 4050
lime-shale-sand 4260
Total Depth

TOPS:

Wabamsee 2459
Topeka 2659
Lansing 3104
Cherokee 3796
Morrow shale 4103
U. Morrow sandstone 4148 & 4156

PERFORATIONS:

4154-4156'; squeezed w/50 sx cem.
4148-4152'

This well was not treated. After
perforations, bailed 75 gal.
Salt Water per hr..

Temporarily Abandoned.