

DRILLERS LOG

-EB : 1971

FEB 27 1971

Elev. 3478' N

INTERSTATE 1-22

Location: SW NE
Section: 22-34S-43W
Morton County, Kansas
Company: Evans & Trigg
Contractor: Davis Drlg., Inc.

Comm: 12-3-70
Comp: 12-22-70
RTD: 4888'
Casing: 8 5/8" @ 1169' KB
6 50 24 Cem

Dry/miss

0	200	Sand & Redbed
200	465	Redbed & Shale
465	913	Redbed, Sand & Shale
913	980	Shale
980	1169	Shale, Sand & Lime
1169	1390	Shale & Sand
1390	1902	Sand
1902	2226	Sand & Shale
2226	2641	Shale
2641	3787	Lime & Shale
3787	3873	Shale
3873	4062	Lime
4062	4187	Shale
4187	4258	Shale & Lime
4258	4358	Shale
4358	4461	Lime, Shale & Sand
4461	4478	Lime
4478	4548	Lime & Sand
4548	4888	Lime
4888		Total Rotary Depth

8 5/8" casing cemented at 1169'
W/200 sacks common W/3% CC, 450
sacks HWT W/2% CC. Plug down at
2:15 a.m. 12-6-70.

5 1/2" 4888' 200' r

Log Left

Heebner	3004
Gansing	3080
Marmaton	3565
Cher	3790
Monow Sh	4090
U. " "	4232
Keyes	4508
Miss. Chert	4584
St Gen	4712
St Louis	4798

I certify that this is the true and correct copy of the above
log, to the best of my knowledge.

Jack E. Trigg

Subscribed and sworn to before me this 22nd day of February

1971.