

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


32-34-43W

Company- ANADARKO PRODUCTION CO.
 Farm- Interstate Unit No. 78

SEC. 32 T. 34 R. 43W
 SE SE NW
 2690' NSL, 2190' EWL

Total Depth. 4291'
 Comm. 10-24-65 Comp. 11-3-65
 Shot or Treated.
 Contractor. Service Drilg. Co.
 Issued. 3-12-66

County Morton
 KANSAS



Elevation. 3541' C.L.

Production. Wtr. Injection.

CASING:

7" 1229' w/800 sx cem
 3½" 4288' w/100 sx cem.

Figures Indicate Bottom of Formations.

sand, red bed	216
Gyp, sand	1128
shale, sand	1230
red bed, shale	1240
shale, Anhydrite	2455
shale, anhydrite, lime	2958
shale, lime	3825
lime	4038
lime, shale	4290 RTD
lime, shale	4291
Total Depth	

TOPS: SCOUT

Morrow	4128
Morrow sand	4187
B/Morrow sand	4224

OIL OR GAS SANDS OR ZONES-PERFORATIONS-ACIDIZING

U. Morrow sand 4190--4222' w/64 shots 2,000 gals.