

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

32-34-43W

Company- PANHANDLE EASTERN PIPE LINE COMPA NY
Farm- Scott No. 1

SEC. 32 T. 34 R. 43W

C NW/4

1320' S of NL & 1320'
E of WL of section

County Morton KANSAS

Total Depth. 4180'


Comm. 5-23-56

Comp. 7-1-56

Shot or Treated.

Contractor. Garvey Drilling Company

Issued. 12-1-56



CASING:

Elevation. 3540'

8 5/8" @1247' w/550 sx cem.

5 1/2" @4178' w/800 sx cem.

Figures indicate Bottom of Formations.

Production. OPEN FLOW
11,175 MCF

SOURCE OF DATA; Driller's Report

sand & red rock	190
sand, rock & Gypsum	535
red rock & Gypsum	875
Gypsum, sand & rock	1115
Gypsum & red bed	1225
Anhydrite	1249
sand, shale & shells	1990
shale & lime	3455
lime	4061
lime & shale	4110
lime, sand & shale	4180
Total Depth	

WELL TREATMENT RECORD

Acidized w/500 gal Mud Acid on 6/11/56

Fracturized w/8000 gal frac w/1# sand per
gallon on 6/11/56;

Acidized w/1000 gal 15% acid on 6/12/56

Acidized w/1000 gal 15% acid on 6/17/56

Acidized w/1000 gal 15% acid on 6/20/56

Acidized w/1000 gal 15% acid on 6/24/56

PERFORATIONS

4123'-4133'

2881'-2888'; 2870'-2878'; 2846'-2852';

2854'-2858'; 2864'-2860'; 2818'-2823';

2800'-2807'; 2735'-2794'; 2773'-2779';

All perfs from 2888'-2735' were squeezed.

SCOUT TOPS:

Morrow Shale 4119

Morrow Sand 4121

REMARKS;

OPEN FLOW, After Acid 26,600 MCF

State Deliverability Test

13,700 MCF — RP 953#.