

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. MUSGROVE PETROLEUM CORPORATION
Farm. Wiker No. 4

SEC.

32-34-43W
32 T. 34 R. 43W
NE SW NW

Total Depth. 4576

Comm. 5-18-55

Comp. 6-6-55


Shot or Treated.

Contractor. Musgrove Petroleum Corporation

Issued. 1-7-56

County Morton

KANSAS



Elevation. 3546 KB

Production. 311 BOPD

CASING:

8 5/8 @ 1247' w/ 600 sx cmt.
5 1/2 @ 4572.5' w/ 225 sx cmt.

Figures Indicate Bottom of Formations.

sand	30
sandy shale	60
shale, shells & red rock	175
shale & shells	380
red bed	465
red rock & shale	635
shale & lime	785
anhydrite	814
shale & shells	1150
anhydrite & shale	1208
shale & anhydrite streaks	1235
anhydrite	1270
shale, sand & anhydrite strks	1330
sand & shale	1723
shale & shells	2180
shale	2251
lime & shale	3990
lime	4021
lime & shale	4084
lime, shale & chert streaks	4100
lime & shale	4182
shale w/ sand streaks	4244
shale & sand	4330
shale	4400
lime & shale	4461
sand & shale	4570
shale	4576
Total Depth	

SCOUT TOPS:

Topeka	2748
Lansing	2978
Morrow shale	4084
Lower Morrow shale	4127
Purdy	4198
Upper Keyes	4466
Lower Keyes	4501