

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

30. 34 - 43W


Company- STANOLIND OIL & GAS COMPANY
Farm- Frank H. Scott No. 1

SEC. 30 T. 34 R. 43W
C SE NE
660' N of SL & 660' W of EL

Total Depth. 4600'
Comm. 12-31-55 Comp. 1-18-56
Shot or Treated.
Contractor.
Issued. 2-18-56

County Morton

KANSAS



CASING:
8 5/8" 1208' cem w/800 sx

Elevation. 3510' DE

Production. Dry

Figures indicate Bottom of Formations.

surface soil and sand	132
clay and sand	200
clay and shale	400
shale	528
shale & clay	809
shale & sand	1058
gyp & red bed	1165
anhydrite	1208
anhydrite & shale	1343
shale	1853
anhydrite & shale	2163
shale & lime	2395
shale	2425
lime & shale	2845
lime	2870
lime & shale	4012
lime	4025
lime & shale	4600
Total Depth	

Tops:	
Topeka	2722
Lansing	2956
Marmaton	3648
Purdy	4210
Keys	4520
Mississippi	4574

Ran Electric logs w/Microlog and Micro Caliper Surveys

DRILL STEM TESTS:

#1 3628-3654', open 1 hr., closed 1/2 hr.
Recovered 600' of drilling fluid, no gas.
IFP 230#, FFP 280#, BHP 1380#.

#2 4206-4227', open 1 hr., closed 1/2 hr. Rec.
2400' of salt water. IFP 150#, FFP 1200#,
BHP 1300#.

#3 4440-4480', open 45 min, closed 45 min, Rec.