

REVISION
29-34-43W

State Geological Survey
WICHITA BRANCH

S. 29 T. 34 R. 43 W

Loc. 990' FN & EL

County Morton

Anadarko Production Company

P. O. Box 351, Liberal, Kansas 67901

Lease Name

ROLL "C"

990 feet from (N) (X) line 990 feet from (E) (W) line

Geologist

KTM Drilling, Inc.

Jim Druyff

Date Completed _____

5/10/81

5/28/81

Total Depth

P.B.T.D.

1234'

1234'

Directional Deviation

Oil and/or Gas Purchaser

not applicable

Panhandle Eastern Pipeline Co

Locate well correctly

Flex.: Gr. 3480.2

DE 3484.2' KB 3485.2'

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	450'	Common	500	3% CaCl
Production	7-7/8"	5-1/2"	14#	1192'	Litewate	350	D-65
					SS Pozmix	150	D-65

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			None		
Size	Setting depth	Packer set at			
None					

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
None	

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
SI for Pipeline		Flowing			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	0 bbls.	362 MCFD		0 bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
To be sold.			1216-34' Red Cave Open Hole		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Anadarko Production Company

DESIGNATE TYPE OF COMP. OIL, GAS,
DAY, TIME, SYMBOL, ETC.
29-34-43W

Well No.

#1

Lease Name

ROLL "C"

Gas

S 29 T 34 R 43 ^{EC}
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

Sand, red bed and clay

0'

434'

Red clay and anhydrite

434'

580'

Red bed and red clay

580'

725'

Anhydrite and shale

725'

880'

Anhydrite and glor.

880'

1181'

Anhydrite

1181'

1193'

Anhydrite, Silt and Sand

1193'

1234'

Total Depth

1234'

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Signature

Paul Campbell, Division Production Manager

Title

May 29, 1981

Date