

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


29-34-43W

Company. ANADARKO PRODUCTION CO.
Farm. Switzer "A" No. 1

SEC. 29 T. 34 R. 43W
C NW

Total Depth. 3035'
Comm. 3-23-61 Comp. 3-29-61
Shot or Treated.
Contractor. Garvey Drlg.
Issued. 9-16-61

County Morton
KANSAS



Elevation. 3489.72' GL

Production. 731,000 CFG

CASING:

8 5/8" 565' cem w/350 sx.
4 1/2" 3015' cem w/50 sx.

Figures Indicate Bottom of Formations.

sand 30
sand & gypsum 150
gypsum & red shale 350
red bed & gypsum 776
sand & shale 1190
Anhydrite 1209
sand & shale 1450
shale, sand & lime 1879
shale & lime 2880
lime 2964
shale & lime 3035
Total Depth

TOPS: SCOUT

Wabaunsee 2514
Topeka 2700
Gr. Lansing 2929

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING & FRACTURING INFORMATION

Name	From	To	No. of Shots	Gallons Used	Kind Used
Lansing	2936	44	16	1500	15%
Topeka	2729	73	32	10000	7½%