

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas


29.34-43W

Company- J. M. HUBER OIL COMPANY
Farm- U. S. A. "D" No. 3

SEC. 29 T. 34 R. 43W
C NW SE

Total Depth. 4250' driller, 4251' Schlumberger
Comm. 1-7-55 Comp. 1-20-55
Shot or Treated.
Contractor. Huber Oil Company
Issued. 4-13-57

County Morton
KANSAS



Elevation. 3508 D. F.

Production. 669 BOPD

CASING:

8 5/8" @1200' w/750 sx cem.
5 1/2" @4250' w/200 sx cem.
2 1/2" @4185'

Figures indicate Bottom of Formations.

BHP 1264 psig. G.O.R. 1230:1
4% wtr.

NO LOG AVAILABLE

Surveys Made

Schlumberger Electric Log from
1203' to 4251'. Micro Log and
detailed from 2300' to 4246'.
McCullough Gamma Ray Log from
3900' to 4210'.

No Drill Stem Tests taken.

No Cores Taken

Perforations

103/4166-4193'

ELECTRIC LOG TOPS

Topeka	2713
Lansing	2941
Morrow Shale	4075
Top Morrow Sand	4166
Base/Morrow Sand	4204

Completion Record:

Ran 5 1/2" csg. to 4250'
Cleaned out to 4219'
Ran McCullough Gamma Ray
Log from 3900' to 4210'
Perforated 8/4202-4204.
Tested well; made an estimated
5 to 6 barrels of salt water
per hour w/show of oil,
Squeezed w/25 sacks of cement
to 4000' pressure. Dis-
placed 14 sx into formation.
Cleaned out to 4194'
Perforated 8/4192-4194. Tested
well; swabbed 3 to 4 bbls of
oil per hour. Perforated
56/4178-4192. Well flowed
after 1 1/2 hr. for 25 min. and
died. Wellflowed after an
hr. for 20 min. and died.
Perforated 48/4166-4178.
Well flowed 160 bbls. oil