

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


29-34-43W

Company- J. M. HUBER OIL COMPANY
Farm- U. S. A. "D" No. 4

SEC. 29 T. 34 R. 43W
C NE SE

County: Morton KANSAS

Total Depth. 4278' Schlumberger 4272' Driller
Comm. 1-27-55 Comp. 2-7-55
Shot or Treated.
Contractor. J. M. Huber Corporation
Issued. 4-13-57



Elevation. 3524' DF

Production. 130 bbls of oil
4 1/2 % salt wtr.
24 hr productivity test

Figures indicate Bottom of Formations.

NO LOG AVAILABLE

SURVEYS:

Ran Schlumberger Electrical
Log from 1200 to 4278';
detailed and microlog and
detailed from 2300' to 4272'.
Ran Perf. Guns Atlas Corp.
Gamma Ray Log to 4238'.

PERFORATIONS:

4226-28' w/8 shots (salt-
water w/scum of oil-squeezed
off)
4226-28' w/8 holes (squeezed
off)
4218-20' w/8 shots (salt-
water - squeezed off)
4196-4210' w/ 4 shots per
foot- oil w/show of water

Pay 4196-4210'

TOPS

Topeka	2734
Lansing	2964
Morrow shale	4095
Morrow sand	4135-47'
	4199-4230'

Completion Report

Ran 5 1/2" to 4274' Cleaned
out to 4239' Ran Perforating
Guns Atlas Corp. Collar Log
to 4239'. Perforated 4226-28
w/8 shots. Ran tubing :4210'
Packer set 4223'. Squeezed
w/50 sx 3500# pressure.
Perforated 4226-28 w/8 holes.
Ran Packer dry. Ran squeeze
packer and squeezed w/50 sx

w/8 shots. Ran Packer dry and
tested. Squeezed w/25 sx 3500#
Perforated 4196-4210' w/4 shots
per ft. Ran tubing to 4208'
Tested swabbing thru tubing
for 10 hrs. well making
estimated 7 barrels of oil
w/show of water.