

AS DRILLERS LOG

State Geological Survey
WICHITA BRANCH

13-127-20331
3-34-43W
S. 3 T. 34S R. 43 W

No. 15 — 129 — 20,331
County Number

Loc. C SW/4

County Morton

Operator

ANADARKO PRODUCTION COMPANY

Address

P. O. BOX 351, LIBERAL, KANSAS 67901

Well No.

1

Lease Name

INTERSTATE "O"

Footage Location

1250 feet from (X) (S) line

1250 feet from (X) (W) line

Principal Contractor

Gabbert-Jones, Inc.

Geologist

None

Spud Date

9/2/77

Total Depth

1415'

P.B.T.D.


1378'

Date Completed

Oil Purchaser

640 Acres

N



Locate well correctly

Elev.: Gr. 3626.3'

DF KB

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	378'	Common	300	3% cc
Production	7-7/8"	4-1/2"	10.5#	1414'	Lite Water Poz	200 150	4% gel 0.2% D-31

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			3	Sch. 3-3/8 Hyper II	1376-80'
			2	McCullough	1372-76'

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1,000 gals 7-1/2% Fe Acid w/Clay stabilizer	1376-80'
Squeeze cmted w/100 sxs Common	1376-80'
500 gals Acetic Acid, 1000 gals 7-1/2% Fe	1372-76'

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
Non-Productive		Swab Test on 11/1/77			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	0 bbls.	TS/TM	MCF	2.5BPH bbls.	CFPB
position of gas (vented, used on lease or sold)			Producing interval(s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

DRY HOLE

ADARKO PRODUCTION COMPANY

Well No.

Lease Name

1

INTERSTATE "O"

S. 3 T. 34S R. 43^{EX} W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface Clay-Sand-Redbed	0'	330'	Welex	
Redbed	330'	400'	Acoustic	377-1409'
Redbed-Anhy-Sand	400'	940'	Velocity	
Anhy-Sand-Anhy	940'	1415'	Gamma	
TOTAL DEPTH		1415'	Caliper Log	
PBTD		1378'		
			Welex Fracture	
			Finder Micro-Seismo	
			Gram Log	400-1407'
			Schlumberger	
			Neutron Log	830-1400'
			Schlumberger	
			Perforating	
			Depth Control	800-1352'

USE ADDITIONAL SHEETS, IF NECESSARY TO COMPLETE WELL RECORD.

Date Received

Paul Campbell
Signature

Paul Campbell, Division Production Manager

Title

April 12, 1978

Date

LS80HS

3-3-1-13M