

3-34-43W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PANHANDLE EASTERN PIPE LINE CO.
Farm- Morissee No. 1

SEC. 3 T. 34 R. 43W
NW SE NE
2780' NSL, 4030' EWL

Total Depth. 3195'
Comm. 5-23-65 Comp. 6-10-65
Shot or Treated.
Contractor. Moran Bros.
Issued. 11-13-65

County Morton
KANSAS



Elevation. 3616' G.L.

8 5/8" 632' w/350 sx cem
5 1/2" 3194' w/300 sx cem.

Production. 3670 MCFGPD

Figures Indicate Bottom of Formations.

surface sand 41
red bed 787
Anhydrite, salt, shale,
sand 1537
Anhydrite, shale 2570
shale, lime 3195
Total Depth

TOPS: SCOUT
B/Cimaron 1366
Red Cave 1379
Wabaunsee 2666
Topeka 2873
Greenwood Lansing 3132

PERF: Lansing 3136-41 w/41 shots.
Topeka 3006-12 w/24 "
" 2965-70 w/20 "
" 2842-46 w/16 "
" 2926-34 w/32 "

ACIDIZED: Lansing w/500 gals.