


Farm- Oberley No. 1

SW SW SW NE
2383' f NL, 2310' FEL of sec.

County Morton KANSAS

3-34-43W

Total Depth. 3250
Comm. 1-21-55 Comp. 1-29-55
Shot or Treated.
Contractor. Garvey Drlg Co.
Issued. 6-18-55



CASING:
10 3/4" 668' cem w/350 sx
7" 3249' cem w/300 sx

Elevation. 3620.3'

Production. O.F. 14,306,000 gas

Figures indicate Bottom of Formations

surface sand 210
red bed 610
red bed, gyp 657
red bed 1705
red bed, anhydrite,
shale 2020
red shale, sandstone,
anhydrite 2331
dolomite, lime 2438
shale red, limestone,
dolomite 2571
lime, shale 3177
lime 3250
Total Depth

Tops:
Wabunsee 2664
Topeka 2895
Lansing 3131

Perforate: 3137-3148 squeezed
3157-3161 "
3177-3180 "
3188-3193 "
3198-3206 "

Re-Perf. 3130-3142

Perforate: 3015-3022
2998-3012
2963-2969
2941-2954
2924-2934
2909-2916
2876-2886
2872-2876
2865-2870
2847-2853
2838-2842
2824-2833

Acidized on:
2-9-55 w/1000 gals of 15% acid
2-13-55 w/1000 " " 15% "
2-14-55 w/1000 " " 15% "
2-15-55 w/4000 " " 15% "
2-16-55 w/1000 " " 15% "
2-16-55 w/4000 " " 15% "
2-17-55 w/1000 " " 15% "
2-18-55 w/1000 " " 15% "
2-26-55 w/1000 " " 15% "
2-27-55 w/4000 " " 15% "

RP 427.2#