

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


7-34-43W

Company- CITIES SERVICE OIL COMPANY
 Farm- Interstate "B" No. 1

SEC. 7 T. 34 R. 43W
 CWL E/2 SE SW

Total Depth. 4830
 Comm. 5-18-53 Comp. 4-29-53
 Shot or Treated.
 Contractor.
 Issued. 10-31-53

County Morton
 KANSAS



CASING:

13 3/8" 535'
 5 1/2" 4710' com. w/500 sx

Elevation. 3592

Production. 8,460,000 Gas

Figures indicate Bottom of Formations.

sand, clay	260
red bed, sand	315
sand	435
shale red, clay, sand	558
red bed, shale, sand	850
sand, shale	1300
sand, anhydrite	1375
shale, lime, anhy.	1610
shale, lime	2155
shale, lime, gyp	2310
shale, lime	3290
shale, lime	3495
shale	3560
shale, lime	3650
shale, chert	3696
shale	3770
shale, lime	3950
sand, shale, lime	3975
shale, lime	4095
shale, lime, chert	4125
shale, lime	4250
shale, lime, strks	4310
shale, lime	4375
shale, lime	4440
shale, lime strks	4535
shale	4595
shale, sand	4646
shale, lime, sand	4741
lime	4759
shale, lime, sand	4830
Total Depth	

Scout Tops:	
Anhydrite	1280
Topoka	2795
Lansing	3032
Marmaton	3515
Cherokee	3765
Morrow Shale	4264
Morrow Sand	4570
Chester	4634
St. Genev.	4780