

K.C.S. LIBRARY

KANSAS

7-34-43W

WELL COMPLETION REPORT AND DRILLER'S LOG

State Geological Survey
WICHITA, BRANCH
AUG 8 0 RECD

S. 7 T. 34s R. 43
1250' from E line & X
Loc. 1250' from S line W

API No. 15 — Morton — 15-129-20,406
County Number

County Morton

Operator Edgar W. White

640 Acres
N

Address 701 Vilymaca St., Elkhart, Ks 67950

Well No. 5 Lease Name Interstate Red Cave


Footage Location
1250 feet from ~~1000~~ (S) line 1250 feet from (E) ~~1000~~ line

Principal Contractor Gabbert Jones Inc.

Geologist

Spud Date 10-6-79 Date Completed 7-30-80 Total Depth 1460 P.B.T.D. 1460

Directional Deviation Oil and/or Gas Purchaser



Locate well correctly

Elev.: Gr. 3672

DF _____ KB _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	20	473'	Halliburton	375	3% CC
Long string	7 7/8"	4 1/2"	10.5	1458'	Halliburton	200 sacks HL 75 sacks Reg.	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	Omega Jet	1401-1404
			2	Omega Jst	1408-1416

TUBING RECORD

Size 2 3/8" Setting depth 1440' Packer set at none

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
750 BBL Foam Frac, 3% gelled Hcl plus 10-20 sand	1401-1404
800 gal. Hcl; 10,000 Gal. foam frac plus 3% gelled acid & 100 sks 10/20 frac sand	1408-1416

INITIAL PRODUCTION

Date of first production not on line Producing method (flowing, pumping, gas lift, etc.) flowing with pumping unit pumping

RATE OF PRODUCTION PER 24 HOURS
Oil _____ Gas 50 MCF Water 20 bbls. Gas-oil ratio _____ CFPB

Disposition of gas (vented, used on lease or sold) Gas contract with Coastal State Gas Producing interval (s) 1401-1404 and 1408-1416

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Edgar W. White

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Gas

Well No.

5

Lease Name

Interstate Red Cave #5

S 7 T 34 S R 43 ^X/_W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
See complete Drillers Log attached				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Edgar W. White
Signature

Owner

Title

7-30-80

Date

89015

J-34-113M

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

7-34-43W

Red Cave #5
NE/4 Sec 7-34S-43W
Morton County Kansas

Commenced: 10-6-79

Completed: 10-8-79


OPERATOR: Edgar W. White

Depth		Formation	Remarks
From	To		
0	162	Sand	Ran 12 jts of 8 5/8" csg
162	476	Redbed	set @ 473' Cemented w/
476	1040	Sand	375 sks Common 3% CC
1040	1270	Shale	PD @ 12:30 a.m. 10-7-79
1270	1460	Sand-Shale	
	1460 - TD		Ran 37 jts of 10# 4 1/2" csg
			set @ 1458' Cemented w/
			200 sks H.L. - 75 sks
			Regular
			PD @ 6:30 p.m. 10-8-79

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.


JAMES S. SUTTON II

Subscribed and sworn to before me this 10th day of October, 1979.


ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1983.