

WELL COMPLETION REPORT AND
DRILLER'S LOG

API No. 15 — 129 — 20,418
County Number

Operator
Anadarko Production Company

Address
P. O. Box 351, Liberal, Kansas 67901

Well No. 4 Lease Name INTERSTATE "D"


Footage Location
660 feet from (N) line 660 feet from (W) line

Principal Contractor Geologist
Gabbert-Jones, Inc.

Spud Date Date Completed Total Depth P.B.T.D.
12/4/79 12/19/79 5150

Directional Deviation Oil and/or Gas Purchaser
3/4 deg @ 4430' Dry Hole

S. 9 T. 34S R. 43 Ex W
Loc. NW NW
County Morton
640 Acres
N



Locate well correctly
Elev.: Gr. 3632.9
DF 3635 KB 3636

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	24#	1347'	Pozmix Common	600 200	4% gel 2% CaCl 2% CaCl

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production Producing method (flowing, pumping, gas lift, etc.)
Dry Hole

DATE OF PRODUCTION R 24 HOURS	Oil	Gas	Water	Gas-oil ratio	CFPB

Disposition of gas (vented, used on lease or sold) Producing interval(s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Anadarko Production Company

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No.

4

Lease Name

INTERSTATE "D"

DRY HOLE

S 9 T 34 S R 43 $\frac{1}{2}$ W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface Clay-Sand	0'	140'		
Redbed	140'	563'		
Redbed-Anhydrite	563'	907'		
Redbed-Anhydrite-Sand	907'	1095'		
Sand-Redbed	1095'	1253'		
Redbed-Anhydrite	1253'	1348'		
Anhydrite-Shale	1348'	1660'		
Lime-Shale	1660'	5150'		
RTD		5150'		
DST #1 4658-75 (Morrow) 30-60-60-120, op w/vry wk blow, rec 70' wtr mud, IFP 14-43, ISIP 977 (60), FFP 43-71, FSIP 977 (120), HP 2198-2184.				
DST #2 4694-4740 (St Louis) 30-30-60-120, op w/vry wk blow thruout, rec 350' SW-N.S., IFP 32-95, ISIP 983 (30), FFP 95-175, FSIP 1014 (120), HP 2282-2250.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Signature

Paul Campbell, Division Production Manager

Title

January 4, 19780

Date

8LE0HS

2-34-43M