

12-34-43W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- PANHANDLE EASTERN PIPE LINE CO.
Farm- Hurt No. 1

SEC. 12 T. 34 R. 43W
NW NE SW

Total Depth. 3090

Comm. 4-8-55


Comp. 4-20-55

Shot or Treated Acidized w/ 10,000 gals 15%, 8,000 gals 7½%

Contractor. Moran Brothers, Inc.

Issued. 7-23-55

County Morton
KANSAS



Elevation. 3462.03

CASING:
10 3/4 @ 612' w/ 313 sx cmt.
7 in. @ 3090' w/ 225 sx cmt.

Production. 7,829,000 CFG
RF 419#

Figures indicate Bottom of Formations.

sand & red bed	247
sand, shale & red bed	670
red bed & sand	715
red bed, shale & sand	1235
anhydrite & gyp	1257
shale & red bed	1600
red rock & shale	1850
red rock, sand & gyp	2005
red bed & anhydrite	2173
shale & gyp	2266
anhydrite & red rock	2440
lime & shale	2522
anhydrite & lime	2595
shale, lime & anhydrite	2692
lime & shale	2978
sandy shale & lime	3030
lime & shale	3090
Total Depth	

TOPS:

Wabaunsee	2540
Topeka	2761
Lansing	3000

Perf.: 2947-52, 2891-99, 2876-80
2843-52, 2817-22, 2800-04, 2787-92,
2764-69