

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

16-34-43W

Company PANHANDLE EASTERN PIPE LINE CO.
Farm Interstate "C" No. 1

SEC. 16 T. 34 R. 43W
C NE SW
1980' E of WL 2030' N of SL

Total Depth. 4345

County Morton

Comm. 3-13-57

Comp. 4-6-57

KANSAS

Shot or Treated. Perf. 4SPF/4230-36, 4SPF/4201-06, Fracked w/ 3000

Contractor Nye & Snell Drilling Co. /gal kero. w/ 1/2# sand per gal.

Issued. 7-13-57

	*		

CASING:

7 in. @ 1200' w/ 750 sx cmt.

4 1/2 @ 4327' w/ 150 sx cmt.

Elevation. 3523 GL

Production. 256 BOPD

Figures indicate Bottom of Formations.

gravel & red bed	525
red bed & shells	840
shells, sand & red bed	1210
shale & shells	2330
shale	2540
shale & lime	3465
lime	3630
lime & shale	4195
lime, shale & sand	4290
shale	4345
Total Depth	

TOPS:

Wabaunsee	2518
Topeka	2725
Lansing	3157
Cherokee	3844
Morrow shale	4158
Upper Morrow Purdy	4198

Producing Formation: Upper Morrow
Purdy 4228-4238