


WELL COMPLETION REPORT AND
DRILLER'S LOG

S. 18 T. 34 R. 43 K W

Loc. A C SE

County Morton

640 Acres
N

Locate well correctly

Elev.: Gr. 3536

DF KB

API No. 15 — 129 — 20,403
County Number

Operator

Edgar W. White

Address

701 Vilymaca Street Elkhart, Ks. 67950

Well No.

#3

Lease Name

Red Cave Interstate

Footage Location

1250

feet from (N) line

1250

feet from (E) line

Principal Contractor

Gabbert Jones Inc.

Geologist

Spud Date

9-29-79

Date Completed

7-30-80

Total Depth

1279

P.B.T.D.

Directional Deviation

Oil and/or Gas Purchaser

None

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4'	8 5/8"	20	1256'	Halliburton	325	Class H 3% CC
Long String	7 7/8"	5.5"	14.5	1256'	Halliburton	250 75	Howcolite Class H

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			open hole		1256-1279'

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Drilled open hole with cable tool from bottom of Casing to 1279'. Foam frac w/20,000 gal 80 quality foam w/ 3% gelled acid and 200 sks 10-20 sand	1256' to 1279'

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
not on line	flowing with pumping unit				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	CFPB
	bbls.	bbls.	bbls.		
		12	50		
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
gas not sold			1256'-1279'		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

Interstate Red Cave #3
75' E of SE/4 Sec 18-34S-43W
Morton County Kansas

Commenced: 9-29-79

Completed: 10-1-79


OPERATOR: Edgar W. White

Depth		Formation	Remarks
From	To		
0	414	Sand	Ran 10 jts of 20# 8 5/8" csg
414	728	Sand-Redbed	set @ 410' Cemented w/
728	1167	Sand	325 sks Class H - 3% CC
1167	1257	Sand-Shale	PD @ 12:45 a.m. 9-30-79
	1257 - TD		Ran 35 jts of 14# 5 1/2" csg
			set @ 1256' Cemented w/
			250 sks Howcolite 75 sks
			Class H
			PD @ 8:00 p.m. 10-1-79

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above
Drillers' Well Log is true and correct to the best of my knowledge and belief and
according to the records of this office.

GABBERT-JONES, INC.


JAMES S. SUTTON II

Subscribed and sworn to before me before me this 10th day of October, 1979.


ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1983.