

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOG

API No. 15 — 129 — 20,457
County Number

State Geological Survey
WICHITA, BRANCH


16-34-43W

S. 16 T. 34S R. 43 ^{XX} W

Loc. 1169 FSL & 1353' FWL

County Morton

640 Acres
N



Elev.: Gr. 3498.5'

DF 3502.5' KB 3503.5'

Operator
Anadarko Production Company

Address
P. O. Box 351, Liberal, Kansas 67901

Well No. 10 Lease Name INTERSTATE "C"

Footage Location
1169 feet from ~~XXX~~ (S) line 1353 feet from ~~XX~~ (W) line

Principal Contractor KTM Drilling Company Geologist John Jacobson

Spud Date 11/4/80 Date Completed 11/23/80 Total Depth 1350' P.B.T.D. 1335'

Directional Deviation not applicable ~~XXXXXXXX~~ Gas Purchaser Panhandle Eastern Pipeline Co.

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	388	Common	350	3% CaCl
Production	7-7/8"	4-1/2"	10.5#	1350	Lite-wate SS Pozmix	350 150	.5% D-31 .5% D-31

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	.41 jet	1200-1222'

TUBING RECORD

Size	Setting depth	Packer set at
2-1/16"	1197'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
A/1000 gal 15% MSR + 60 BS	1200-1222'

INITIAL PRODUCTION

FEB 20 1981

Date of first production SI for Pipeline Producing method (flowing, pumping, gas lift, etc.) Flowing

CONSERVATION DIVISION
Wichita, Kansas

RATE OF PRODUCTION PER 24 HOURS Oil --- Gas 516 MCF Water --- Gas-oil ratio --- CFPB

Disposition of gas (vented, used on lease or sold) To be sold Producing interval(s) 1200-1222' (Redcave)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be trans-
mitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation
Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note
Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Anadarko Production Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 10	Lease Name INTERSTATE "C"	GAS
S 16 T 34SR 43 E W		


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand, Gravel & Clay	0'	300'		
Shale & Anhydrite Stk.	300'	385'		
Redbed, red shale & Anhydrite	385'	685'		
Red Clay & Shale	685'	765'		
Sand & Shale Stk	765'	1023'		
Sand, Shale & Anhydrite	1023'	1223'		
Shale & Anhydrite	1223'	1350'		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	
	Signature
	Paul Campbell, Division Production Manager
	Title
	November 25, 1980
	Date

LEHONS)

10-34-43M