

KANSAS

REVISED

16-34-43W

WELL COMPLETION REPORT AND DRILLER'S LOG

API No. 15 — 129 — 20,470
County Number

State Geological Survey
WICHITA, BRANCH

S. 16 T. 34 R. 43 E
W
Loc. 1189 FNL & 1147 FEL

County Morton
640 Acres
N

Operator
Anadarko Production Company

Address
P. O. Box 351, Liberal, Kansas 67901


Well No. 12 Lease Name INTERSTATE "C"

Footage Location
1189 feet from (N) 30 line 1147 feet from (E) 300 line

Principal Contractor KTM Drilling Co. Geologist John Jacobson

Spud Date 11/16/80 Date Completed 12/9/80 Total Depth 1350' P.B.T.D. 1345'

Directional Deviation not applicable Oil and/or Gas Purchaser Panhandle Eastern Pipeline Co.



Locate well correctly
Elev.: Gr. 3543'
DF 3547' KB 3548'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Socks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	368	Common	350	3% CaCl
Production	7-7/8"	4-1/2"	10.5#	1349'	Lite-wate SS Pozmix	350 150	.5% D-31 .5% D-31

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	.46 jet	1286-1312' O.A.

TUBING RECORD

Size	Setting depth	Packer set at
2-1/16"	1264'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
A/1000 gal 15% MSR-100 + 50 BS	1286-1312' O.A.

INITIAL PRODUCTION

Date of first production SI for pipeline conn Producing method (flowing, pumping, gas lift, etc.) Flowing

RATE OF PRODUCTION PER 24 HOURS
Oil bbls. Gas 196 MCF Water bbls. Gas-oil ratio
Wichita, Kansas CFPB

Disposition of gas (vented, used on lease or sold) to be sold Producing interval(s) 1286'-1312' O.A. (Red Cave)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Anadarko Production Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 12	Lease Name INTERSTATE "C"	GAS
S 16 T 34S R 43 E W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand Shale & Redbed	0'	262'		
Shale & Redbed	262'	375'		
Redbed & Shale	375'	718'		
Shale	718'	752'		
Glorietta	752'	757'		
Sand Shale & Anhydrite	757'	851'		
Glorietta	851'	1300'		
Shale & Anhydrite	1300'	1350'		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<p align="center"><i>Paul Campbell</i> Signature</p> <p align="center">Paul Campbell, Division Production Manager Title</p> <p align="center">December 11, 1980 Date</p>
---------------	--

SHD0439

10-30-1980