

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock,

Wichita, Kansas

17-34-43W


Company- Panhandle Eastern Pipe Line Company
Farm- Humble

No. 1-17

SEC. 17 T. 34 R. 43W
C SE
1420' W. fr. EL & 1320'
N. fr. SL. SE/4

County Morton
KANSAS

Total Depth. 3210'
Comm. 5-27-57 Comp. 6-6-57
Shot or Treated.
Contractor. Garvey drilling Co.,
Issued. 11-16-57



Elevation. 3568' G. L.

Productiv. 7435 MCF after acid

Figures indicate Bottom of Formations.

surface soil & sand	40
red bed	638
red bed	800
anhydrite	825
sand & shale	1030
sand & redbed	1650
shale	1897
lime & shale	2215
lime	2325
lime & shale	2435
lime	2482
lime & shale	2685
lime	2759
lime & shale	2906
lime	3210
Total Depth	

Tops:	
Waubaunsee	2547
Topeka	2750
Greenwood Lansing	2985
Lansing	3169

Perforations:

3135-38; 3122-27
2992-3002 sq
2897-2902; 2873-2880;
2849-2854;
2821-2825; 2806-2810;
2798-2801;
2788-2793;

Well Treatment Record:

A/500 gals 15% acid 6/10/57
A/1000 gals 15% acid 6/10/57
A/500 gals 15% acid 6/13/57
A/1000 gals 15% acid 6/17/57
A/5000 gals 15% acid 6/18/57
A/3000 gals 15% acid 6/19/57
Worked w/2000 gals 7½% acid