

KANSAS

17-34-43W^{2117/80} *Jul*
State Geological Survey
WICHITA, BRANCH *JAN*

WELL COMPLETION REPORT AND DRILLER'S LOG

API No. 15 — 129 — 20,458
County Number

Operator
Anadarko Production Company

Address
P. O. Box 351, Liberal, Kansas 67901


Well No. 6 Lease Name INTERSTATE "B"

Footage Location
1320 feet from (N) (S) line 1320 feet from (E) (W) line

Principal Contractor KTM Drilling Company Geologist John Jacobson

Spud Date 12/1/80 Date Completed 12/18/80 Total Depth 1335' P.B.T.D. 1325'

Directional Deviation not applicable Oil and/or Gas Purchaser Panhandle Eastern Pipeline Co.



Loc. C SW/4
County Morton
640 Acres
N
Locate well correctly
Elev.: Gr. 3548'
DF 3552' KB 3553'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	368	Common	350	3% CaCl
Production	7-7/8"	4-1/2"	10.5#	1334'	Lite-wate SS Pozmix	350 150	.5% tic .5% tic

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			2	.46 jet	1242-1276' O.A.
Size	Setting depth	Packer set at			
2-1/16"	1245'				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
A/1000 gal 15% Spearhead + 75 BS	1242-76' O.A.

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)			
SI for pipeline	Flowing			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	-- bbls.	201 MCF	-- bbls.	-- CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)	
To be sold			1242-76' O.A. (Redcave)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be trans- mitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Anadarko Production Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 6	Lease Name INTERSTATE "B"	GAS
T 17 S 34 R 43 W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand & Clay	0'	62'		
Sand Shale & Lime Stone	62'	373'		
Redbed & Red Shale	373'	776'		
Anhydrite	776'	813'		
Florietta	813'	1121'		
Anhydrite	1121'	1254'		
Anhydrite & Clay	1254'	1335'		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Paul Campbell
Signature

Paul Campbell, Division Production Manager

Title

December 19, 1980

Date

J-34-113M