


KANSAS DRILLERS LOG

API No. 15 — 129 — 20,362
County Number

S. 19 T. 34 R. 43 ^W
Loc. 3785' FNL & 1813' FEL

County Morton

640 Acres
N



Locate well correctly
Elev.: Gr. 3486.4

DF KB

Operator
Edgar W. White

Address
Drawer O Elkhart, Kansas 67950

Well No. #2 Lease Name
Interstate Red Cave

Footage Location
3785' feet from (N) (S) line 1813' feet from (E) (W) line

Principal Contractor Geologist
KTM Drilling & Ace Well Service

Spud Date Total Depth P.B.T.D.
July 19, 1978 1236' 1236'

Date Completed Well Purchaser Gas
Aug. 30, 1978 Colorado Interstate Gas

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12½"	8 5/8	26	270	portland	cemented	to top
Surface	7 7/8	4 1/2	9.5	917	portland	(Haliburton)	
Production	3 7/8	2 7/8	6.4	1236	portland	(Haliburton)	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
none			two	McCullough	1213-1218
TUBING RECORD					
Size	Setting depth	Packer set at			
none					

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Fractured with 4,000# 20-40 sand. Pumped 2,000 gal 3% Hcl acid with 500 SCF N2 per Bbl. Flushed with N2. Frac. pressure 1,500# at 3 BPM. (Haliburton)	1213-1218

INITIAL PRODUCTION

Date of first production Producing method (flowing, pumping, gas lift, etc.)
not yet on pipe line flowing thru separator

RATE OF PRODUCTION PER 24 HOURS Oil Gas Water Gas-oil ratio
bbbls. 109 MCF 5 bbbls. CFPB

Disposition of gas (vented, used on lease or sold) Producing interval(s)
sold to Colorado Interstate Gas Co. 1213-1218

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

