

90227

5-263W+
 MAP NO. 82
 STATE Kans. COUNTY Morton SEC. 6 TWP. 34S RGE. 43W
 OPERATOR Anadarko Prod. Co. FT. FROM _____ LINE
 WELL NO. 1 FARM NAME Williams "E" FT. FROM _____ LINE
 GREENWOOD ELEV. 3679 GR. 3689E DF 3692 E.K.B.
 FR. 3/29/62 SPUD 4/2/62 COMP. 5/22/62

PERMANENT FILE COPY

CONT. Wakefield Drlg. Tools /GEOL. _____

NAME PRODUCING INTERVAL COMPLETION RECORD FROM - TO PERF. W/HOLES TREATMENT RECORD

a _____
 b _____
 c _____
 d _____

a I. P. OIL/DIST. WTR. GAS M.C.F.P.D. CHK. HRS.

b " " " " " "

c " " " " " "

d _____

D & A

D & A ()

SIP# _____ FI TP # _____ FI CPH _____ SIBHP _____

GOR. _____ GR. _____ PBDT _____ TD 4978

SIZE DEPTH CASING - CEMENT RECORD SIZE DEPTH W/SAX.

13-3/8" 633 400

8-5/8" 1369 200

OPERATOR Anadarko Prod. Co. WELL NO. 1 Williams "E" ELEV. 3679 Gr.

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
-------------	-------	---------	------------	-------	---------

Gr Tops & Datums

RTD (St Gen) 4978 -1299	Red Cave	not called
	B/Cimm	1418 +2261
	Waub	2704 + 975
Lost Circ. - no interval	Top	2910 + 769
<u>DST #1 (Red Cave) 1368-1455,</u>	Grnwd Lans	3156 + 523
Op 30", R 5' M, IBHP 174#	Lans	3386 + 293
/20", IFP 22#, FFP 10#,	Marm	3892 - 213
FBHP 43#/20"	Chero	4065 - 386
<u>DST #2 (Morr) 4470-80,</u>	Morr Form	4398 - 719
Op 1 hr., R 180' SGCM +	Up Sand	4469-4504 -790
2065' SW, IBHP 1096#/30"	Up Sand	4508-36 -829
IFP 327#, FFP 1096#,	Morr"G"Sd	4721-4805 -1042
FBHP 1116#/30"	Keyes Sd	4815-4918 -1136
<u>DST #3 (Up Morr) 4506-49,</u>	Miss	4918 -1239
Op 45", R 360' GCM +	St Gen	4957 -1278
1800' SW, IBHP 1188#/30",		
IFP 646#, FFP 1181#, FBHP 1188#/30"		
RTD 4978, Log		
<u>WLT #1 (Morr) 4787½-90, R 1500 cc filt wtr, IBHP 0#/45",</u>		

FBHP 50/15:

WLT (Lans) 3538-40 $\frac{1}{2}$, op 90 min, rec 1100 cc filt wtr,

IBHP 0/NT, FBHP 690/34:

WLT (Top) 3027 $\frac{1}{2}$ -30, op 61 min, rec 50 cc filt wtr, IBHP 0/NT,

FBHP 100/30:

WLT (Lans) 3663-65 $\frac{1}{2}$, op 1 hr, rec 11,000 cc wtr (form), BHP 0/4,

FBHP 740/10:

WLT (RC) 1435-37 $\frac{1}{2}$, op 1 hr, rec 5100 cc wtr, IBHP 380/5, FBHP

340/25:

D & A.