

90225

10-185W Map No. K-82 O W W O

OPER ANADARKO PROD CO. - Liberal, Ks.

WELL #1 INTERSTATE UNIT

STATUS Not avail

FIELD Interstate (Red Cv Gas & Mrw O&G)

I.P. Inj Well - Rate 22 BWPM, Purdy 4356-86



S-T-R 8-34S-43W

SPOT C NE SW

CO MORTON (Ks)

ELEV 3638 DF

(Old DF Logs:)

Wabq	2643	/	995
Top	2842	/	796
Grn Lan	3082	/	556
Lans	3301	/	337
Chero	3970	-	332
Mrw sh	4298	-	660
Purdy	4352	-	714
B/Purdy	4406	-	768
LTD	NA		
OTD	4450	-	812

OLD INFO: (Was P.E.P.L. #03 Smith "B") (Old Spd 11-1-58, 8" @1204' w/700 Sx.)

DST #1 () 4288-4358, Op 60", GTS/6", TSTM, R 1410' SMCO, ISIP NA, FP's 205#-390#, FSIP 1190#/20", OTD 4450, Sj Log, 4" @4430' w/115 Sx.

CO 4372 PBTD, GRN Log, Pf 8/4353-55 (Purdy) § 4 BOPH NW-NT, nat, POP, Co Pump 25 BOPD-NW, Purdy sd 4353-55, Gr 40 deg, Completed on 2-25-59

NEW INFO: (10-14-65)
Pull T&R, CO 4388, Pf 60/4356-86 (Purdy) 2000A, Set 2-7/8 tbg to 4269 (Injection well - Water flood project) Inj rate: 22 BWPM, Purdy 4356-86 - FIRST REPORTED & COMPLETED on 10-14-65

Data Inc

MISCEL DATA	GEOLOGICAL _____	ELEV <u>3641 OKB</u>	SPUD DATE <u>11-1-58</u>
	FTG _____	_____	DRLG COMP _____
	SUPPT _____	_____	FR by DATA <u>10-14-65</u>
	CSG <u>8" @1204 w/700 sx. 4" @4430 w/115 sx.</u>	_____	COMP by " <u>10-21-65</u>