


(100' E of gravel)
(1250' FSL + 1390' FWL)

8-96W Map No. K-82
OPER J.M. HUBER CORP
BORGER, TEXAS
WELL #2 (RC) AUSTIN (TWIN)
TR HOLM DRLG.
FIELD INTERSTATE FIELD (MULTI PAY)
I.P. GA 4,250,000 CFGPD, RED CV 1297-1304



S-T-R 10-34S-43W
SPOT APP C SW
CO MORTON (KS)
ELEV 3543 KB

SPUD 4-22-66 NO SURF SET

RTD 1368, 4 1/2" 1367 W/300 SX.
PF 14/1297-1304 (RED CV), GSG, OP 12 HRS, NO FLU, GA
600,000 CFGPD, 500A + 20 BBL TREATED FLUSH; FRAC 10,000
GAL WTR + 10,000# SD, OP 5 HRS, GA 3,000,000 CFGPD, VERY
WET, 72 HR SIP 300#
GA 1,000,000 CFGPD + 4 1/2 BWPH/14 HRS, SIP 190#, GA 250,000
CFGPD-NW 3/16" CK/NT, GA 350,000 CFGPD + 3 BW 1/4" CK/2
HRS, GA 600,000 CFGPD + 18 BW 3/8" CK/2 HRS, GA 1,000,000
CFGPD + 10 BW 1/2" CK/2 HRS, GA 1,200,000 CFGPD + 3 1/2 BW
5/8" CK/45"
IND OF; GA 4,250,000 CFGPD, SIP 329#, RED CV 1297-1304 -
COMPLETED ON 8-5-66

(LOG) KB
B/SC 1275 +2268
RED CV SS 1287 +2256
B/" " " 1320 +2223
LTD NA
RTD 1368 +2175

Data Inc

MISC DATA

GEOL _____ ELEV 3540 DF
FTG 1250' FSL X 1390' FWL OF SW/4 3537 GR
SUPPT _____
CSG NO SURF SET 4 1/2" 1367 W/300 SX.

8-5 3539 E D F
3537 G L

SPUD DATE 4-22-66
DRLG COMP _____
FR by DATA 4-15-66
COMP by " 8-11-66