

★★★★


6

State KANSAS Field _____
 Company PEPL County MOLTON
 Farm INTERSTATE ~~4~~ "B" No. 0-2
 Sec. 17 Twp. 34 Range 43

Spot C SW SW

Contractor MYE + SNELL

Remarks _____



Comm. 7/31/56 Comp. 10/17/56
 Elev. _____ DF 3533 GL 3527 KB _____ TD 4305 PB 4269
 Pay 4225-30

~~STATE POT.~~
 I.P. P 118 BOPD Press. _____
 Casing Record: 13 3/8 _____ 7" 1138/450
 20" _____ 10 3/4 140/250 5 1/2" _____
 16" _____ 8 5/8 _____ 4 1/2" 4304/400

Sample	Log
TTD 214 block & fishy	
AUG 8 # 2795	Wab 2578
AUG 15 DST 4220-45 op 1 hr. 9TS	Appl 2718
1 1/2" TSTM + died by passed GT	CO Lens 2958
SM. OTS ? REVERSED 3800' oil	Lens 3146
rec 100' SW + 100' 9CM. FP	mem 3726
178-800 BHI 1160/20 HH2040	Chem 3834
# 4245	Mouch 4148
DST 4220-4245 op 1 hr.	Purdy 4226
9TS 1 1/2", 87 MFT + died	
rec 3800' oil, 100' mud	
100' SW FP 178-880,	
BHSP 1160' at 4 1/2"	
casing 4304/400;	
MEET, CO 4269, pay	
70/ 4225-4230, rec 19	
WLS oil, 2 lbs swph,	
prop to run thg, run 2 3/8" thg + rods 4247, WOT.	

~~AUG 24 WOT,~~
 SEP 12 ✓ SEP 19 ✓ SEP 26 ✓ OCT 3 ✓

~~OCT 10~~
 State pot. played 118 BOPD.
 OCT 17 1 State potential ~~Bar~~ + ~~Sw~~
 pumped 118 BOPD ~~4%~~ ~~4%~~
 Gr. 39°

AMARILLO TOPS

3527 GL

Topeka 2718 (+809)

Heebner 3023 (+504)

Lansing 3145 (=382)

Morrow 4118 (-591)

"S-2" 4226 (-699) T 14', por 12', C 118 BOPD + 4% XW

TD 4311 (-784)