

\*\*\*\*

5

Field \_\_\_\_\_  
 State Kansas County Morton  
 Company Huber Corp.  
 Farm Block "A" Well No. 5  
 Sec. 20 Twp. 34S Range 43W  
 fr N \_\_\_\_\_ fr E \_\_\_\_\_ fr S \_\_\_\_\_ fr W \_\_\_\_\_  
 of SE NW  
 Contractor Co. Tool  
 Remarks PEPL FO  
 Comm. 10-17-55 Comp. 12-7-55  
 Elev. 3503 df. T. D. 4552 P. B. \_\_\_\_\_  
 Pay 4191-98

I. P. 140/30 PD R. P. \_\_\_\_\_  
 Casing Record: 13 3/8 75/100 7  
 20 \_\_\_\_\_ 10 3/4 \_\_\_\_\_ 5 1/2 4300/650  
 16 \_\_\_\_\_ 8 5/8 1193/600

10-19-55  $\phi$  150' Tops Sample by CW  
 TOP 2693  
 LANY 2920  
 MOR 4072  
~~Ret 8 5/8 @ 1193/600~~  
 $\phi$  3898

NOV 2 1955  $\phi$  4171-4210 m 39' 2507  
28" sd. 70/47%  
11" sh.  
DST 4168-4210 open 40"  
gts 2" 3" g 1,500 m of spray  
one 6" no ret. rec 420 oil  
FP 700-800 - BH 1250/20  
 $\phi$  4440 - 70 m 30'  
18' sh. only sd. - tite, no por - slicko oil.  
12' bl sh.  
DST - 4438-70 op 1 hr. rec 5' mud  
FP 20 - BH 100/20  
DST (Kays) 4500 - 5000  
DST 4467 - 4500 open 1 hr.  
bl. blv. gts 30" TSTM

run 50' v sl: g cm FPO BH 90/20

RTD 4552

DST 4500-52 - 1 hr. gel blue

run 300' Ali g cm + 1900' SW

FP 450-960 BH. 1035/20

run log

set 5 1/2 @ 4300/650

WOC.

log top <sup>by Co</sup>  
top 2694

NOV 9 1955 / DOCT CO 4260

run GR log pf 16/4193-97 Longy 2924

run 2" tub w pknt 4184 Mal 4075

subt 75 g wph. in 1 hr. Mudly sd. 4170

pres to pure tub + heff.

NOV 16 1955

~~run - 63.7 BO in 8 hrs~~

~~for pot of 190 BOPD.~~

~~φ~~

~~GR 39°~~

pf 28/4191-98 - subt on sho oil

+ 7 gal H<sub>2</sub>O ph - re pf 29/4191-98

on sho oil + gas run T A/250 m

subt thru tub - 6 1/2 hrs subt

20 BO + 3 B H<sub>2</sub>O + 5 hr gas

27 hrs subt 408 BO + sho gas

POP

NOV 22 1955 ✓

NOV 30 1955 ✓

DEC 7 1955 state test. 140 BO in 2.4 hrs.

No water

GR 40.2°

φ