
Field _____ 5

State Kansas County Morton

Company Huber

Farm Block "A" Well No. 3

Sec. 20 Twp. 34S Range 43 W
Blk. _____ Survey _____

fr N _____ fr E _____ fr S _____ fr W _____

of NW SE

Contractor Co. Tools

Remarks _____

Comm. 9-17-55 Comp. 11-2-55

Elev. 3442 DF T. D. 4260 P. B. 4180

Pay 4157-4176-#

40.2° br.

I. P. 242.56 BOPD R. P. _____

Casing Record: 13 3/8 80/100 7

20 10 3/4 (5 1/2 4219/600)

16 8 5/8 1100/700

9-21-55 TTD 85', TTD 1120 Tops Sample TOPS

Ø 2435

SEP 28 1955 TTD 4120 July 2898

DST 4100-4120 open 1/2 hr sh 4057

gts 13" g 600 mcf rec U. Purdy 4105

120' ali OCM + 450' ali O + GC SW

FP 90-260 BH 1029/20 Purdy 113-16

Ø 4148-4188 rec 37 1/2' Purdy 4151

3' sh sdy

25' sd. gd. Kong

9 1/2' sh. 4150 = 4148

DST 4147-88 open 55 min

gts in 5" g 360 mcf oil in

47" rec 990' Free Oil + 90' ali Salt

H₂O FP 240-495 BH 1125/20

RTD 4260

running log.

OCT 5 1955 5 1/2 @ 4219/600

PUCT CO 4184

pf 24/4172-76 swb + tested

14 hrs - flowed 151.5 BO

no H₂O + 500 mcf

blew oob collar

bridged plug 1500 - ϕ plug -

OCT 1 2 1955 drone plug to 4180 load
hole ^{with} 41 60 ft 90/4157-4172
run 2" tub @ 4175 subv flow load
flowed 65B new oil in 2 hrs

OCT 1 9 1955 / State test
runned 242.58 BOPD
gr 40.2°

OCT 2 6 1955

~~load for~~ Log tops ^{by 40}
Top 2672
Lang 2904
Mal 4052
Pudgsd 4151

NOV 2 1955

ϕ

2672
2672
2672
2672
2672