


10-262W Map No. K-82 O W W O
OPER ANADARKO PROD CO. - Liberal, Ks.



S-T-R 31-34S-43W
SPOT C NE NE
CO MORTON (Ks)
ELEV 3540 KB

WELL #70 INTERSTATE UNIT
R Service Drlg.
FIELD Interstate (Red Cave & Mrw)
I.P. Wtr Inj Well - Purdy 4203-20

(Old KB Logs:)
Top 2734 $\neq$ 806
Lans 2965 $\neq$ 575
Mrw sh 4100 - 560
Purdy 4202 - 662
Keyes 4466 - 926
LTD 4591 - 1051

OLD INFO: (Was Musgrove Petroleum #1 Brown (Spd 4-27-55, 8" @1266' w/600 Sx.)

DST #1 (Lans) 4014-52, Op $\frac{1}{2}$ hr, Rec 1' M, all Press 0#, RTD 4591, Log, 5 $\frac{1}{2}$ " @4591' w/120 Sx.

CO 4572, 40/4510-20 (Keyes) $\frac{1}{2}$ BOPH/4 hrs, NW, Frac 1500 gal deisel $\neq$ 250A, lost 1d, PB 4500, 40/4468-78 (Keyes) Frac 250 MA $\neq$ 1500 gal deisel, $\frac{1}{2}$ 1d, no sho, PB 4245, 32/4212-20 (Purdy) FU 700' oil/1 hr, 28/4203-10 (Purdy) Flo 20 BOPH/NW/NT, P & flo 293 BOPD, Gr 37.5 deg, Comp June 1955

NEW INFO: (10-27-65)

MICT Oct 1965, Pull tbg, 34/4203-20 (Purdy) 1500A, flush 400 BW, Set tbg to 4200' - Wtr Inj Well - FIRST REPORTED & COMPLETED on 10-27-65

Data Inc

MISC DATA
GEOL _____ ELEV 3536 DF SPUD DATE 4-27-55
FTG _____ DRLG COMP _____
SUPPT _____ FR by DATA 10-27-65
8" @1266 w/600 Sx 5 $\frac{1}{2}$ " @4591 w/120 Sx COMP 10-28-65