

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


21-34-5W

Company- The TEXAS COMPANY
 Farm- L. R. Bird No. 1

SEC. 21 T. 34 R. 5W
 NW NW SE

Total Depth. 4596
 Comm. 8-1-53 Comp. 8-23-53
 Shot or Treated.
 Contractor. Stickle Drilling Co.
 Landed. 10-17-53

County Harper
 KANSAS



CASING:
 10 3/4" 600' cem. w/400 sx

Elevation. 1219' DF

Production. Dry

Figures Indicate Bottom of Formations.

shale & red bed	450
shale & shells	900
lime & shale	2661
lime	2775
lime & shale	3118
lime	3167
lime & shale	3200
sandy lime & shale	3254
shale & lime	3635
sandy shale & lime	3674
sandy lime & shale	3733
sand & shale	3745
shale	3803
shale & lime	3856
sand	3870
sand & lime	3903
lime	4120
shale & lime	4416
shale	4465
shale & lime	4581
lime	4600
Total Depth	
Corrected Total Depth	4596

TOPS:	
Topeka	2650
Douglas	3226
Stalnaker	3594
Kansas City	3843
Layton	3847
Layton Sand	3860
Kansas City Lime	3873
Base Kansas City	4095
Marmaton	4193
Cherokee	4332
Mississippi	4568