

26-34-5W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- SUNRAY MID-CONTINENT OIL COMPANY  
Farm- W. Baker No. 1

SEC. 26 T. 34 R. 5W  
NE NE NW

Total Depth. 4938'  
Comm. 11-5-57 Comp. 11-30-57  
Shot or Treated.  
Contractor. Stickle Drilling Company  
Issued. 3-15-58

County Harper  
KANSAS



CASING:  
3 5/8" 380' cem w/250 sx

Elevation. 1195' DF

Production. Dry

Figures Indicate Bottom of Formations.

surface	0
surface clay & sand	40
shale & shells	265
shale & red bed	281
shale & red bed & shells	320
shale & shells	335
Anhydrite	375
shale & shells	955
lime & shale streaks	1240
shale & lime	1405
lime	1770
lime & shale	1935
shale	2110
shale & lime	2850
sandy lime	3010
lime & shale	3090
sandy lime & shale	3240
lime & shale	3655
sandy lime & shale	3725
lime & shale	3814
lime	3850
Kansas City Lime	3885
lime	3952
lime & shale	4058
shale	4182
lime & shale	4370
shale	4461
Mississippi Lime	4467
Mississippi Lime & Chat	4480
lime	4522
Mississippi Lime	4535
lime	4563
Mississippi	4578
lime	4662
Mississippi Lime	4678
lime	4841
lime & shale	4875
shale	4913
shale & lime	4933
sand	4938
Total Depth	

TOPS:	
Lansing Kansas City	3780
Base/Kansas City (Scout)	4016
Marmaton (Scout)	4098
Mississippi	4461
Viola	4910
Simpson	4933

DST 4919-4938 op. 1 hr. rec. 240' NSW,  
FBHP 2010#.