


3-131W MAP NO. 84 SEC. 5-34S-29W
 STATE Kans COUNTY Meade LOC. C NW NW
 OPER. Thomas & Brewer FT/FR _____ LINE _____
 WELL 1-5 FARM Adams "A" FT/FR _____ LINE _____
 L Novinger East Ext ELEV. 2638 GR. 2646 DF 2649 KB _____
 CO. Rine Drlg., Co. GEOL. Glen Thomas
 INT. 6100' Oil & Gas Test
 F.R. 12-12-62 SPUD 12-11-62 COMP. 3-12-63
 TD. 6070 FM. Chester PBTD. _____
 COMP. RECORD Morr 5885-95 - 40 - 200A & Frac
Flow 150 BOPD thru $\frac{1}{2}$ " choke-Ga 2,310 Mcfgpd
8 5/8" @1483/825 sx. $4\frac{1}{2}$ " @4955/150 sx.



Data Inc.

(KB Spl)

Winf	2832	- 183
Hb	4470	
Tor	4510	
Lans	4638	
Marm	5288	
Chero	5464	
Morr	5800	
RTD	6070	-3421

(KB Log)

Hb	4456	-1807
Tor	4508	-1859
Lans	4640	-1991
Marm	5286	-2637
Chero	5460	-2811
Morr	5804	-3155
Morr sd	5853	-3204
Chest	5947	-3298
LTD	NA	

DST #1 (Morr) 5795-5900, Op 1 hr, R 25' M, IFP 22#, FFP 24#,
 FBHP 88#/30", RTD 6070, Log,
 WLT #1 (Morr) 5893-95 $\frac{1}{2}$, Op 90", R 3600 cc wtr, IBHP 2150#/27 $\frac{1}{2}$ ",
 No FP's, FBHP 50#/5"
 WLT #2 (Chest) 5967 $\frac{1}{2}$ -70', Op 90", R 2000 cc wtr, IBHP 2200#/49"
 No FP's, FBHP not taken, $4\frac{1}{2}$ " 4955/150 sx. Perf 40/5885-95
 (Morr) 200A (15%) § 3 GPH/4 hrs, Frac (20,000 GA x 10,000# Sd),
 Ga 9410 Mcfgpd + $\frac{1}{2}$ BOPH/NT, SIP 1525#/2 hrs, Ga 5000 Mcfgpd
 thru 21/64" ck + $\frac{1}{2}$ BOPH/NT, FCP 1000#, 2 3/8" tbgs @5880', Ga
 5308 Mcfgpd, FCP 825#, FTP 125#, Log, Ga 2,310 Mcfgpd + 61 1/3
 BO/3 hrs, 26/64" ck SI, State Pot: Flow 150 BOPD thru $\frac{1}{2}$ " choke
 Ga 2,310 Mcfgpd, Morr 5885-95 COMPLETED (3-4-63)

LIBERAL ELECTRIC LOG TOPS

2649 KB

Winfield 2832 (-183)

Council Grove 3080 (-431)

Heebner 4480 (-1831)

Toronto 4508 (-1859)

Lansing 4640 (-1991)

Marmaton 5286 (-2637)

Morrow 5804 (-3155)

"S-2" Sand 5881 (-3232) 18/31; ϕ 150 BOPD + 2,300 MCF

Chester 5946 (-3297)

TD 6070