


22-34-6W

Total Depth. 5324
 Comm. 7-25-52 Comp. 9-12-52
 Shot or Treated.
 Contractor. Stickle Drlg Co.
 Issued. 10-25-52

County Harper
 KANSAS



CASING:
 10 3/4" 655' cem w/500 circ.

Elevation. 1278 DF

Production. dry

Figures Indicate Bottom of Formations.

red bed sandy	70
shale	110
sand	120
shale, shells	450
shale shells, salt	580
shale, shells	1245
shale, lime	2090
shale, shells	2110
lime chalky, shale	2200
lime, shale	2838
lime	2867
shale, lime	3160
sand shale, lime	3257
shale, lime	3430
sand shale, lime	3477
shale	3595
sand, shale	3632
sand	3652
sand, shale	3758
shale	3875
lime, shale	3897
lime	4055
lime, shale	4078
lime	4138
lime sandy, shale	4168
lime, shale	4308
lime	4340
lime, shale	4434
sand shale, lime	4489
shale, lime	4549
lime	4582
lime, chert	4645
lime, shale	4678
lime	4728
lime, shale	4739
lime	4796
lime, shale	4866
lime	4886
lime, shale	5040
shale	5185
shale, sand	5239
lime	5324
Total Depth	RTD

Tops:	
Topeka	2784
Kansas City	3866
Mississippi	4548
Kinderhook	4920
Chatanooga	5003

Viola	5028
Simpson Dolo.	5038
Simpson sand	5052
Simpson shale	5137
2nd Simp. Sand	5210
Arbuckle	5256

