

Geological Report

American Warrior Inc.
Turner #1-12
1000' FSL & 530' FWL
Sec. 12 T34S R7W
Harper County, Kansas

James Dilts
Geologist

American Warrior, Inc.

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 11 2010
CONSERVATION DIVISION
WICHITA, KS

General Data

Well Data: American Warrior Inc.
Turner #1-12
NE-NW-SW-SW
1000' FSL & 530' FWL
Sec. 12 T.34S R.7 W.
Harper County, Kansas
API # 15-077-21, 640-0000

Drilling Contractor: Duke Drilling Co

Spud Date: 8/7/2008

Rotary TD Date: 8/17/2008

Rotary TD: 5460'

Elevation: 1332' Ground Level
1343' Kelly Bushing

Casing: Surface 262' 8 5/8" 23# surface casing set at
262' w/195 sx 60/40 3%cc 2%gel
Production 5372' 5.5" 15.5# at 5385' w/200 sx
AA-2 1/4# Flocele

Samples: 10' wet and dry, 3900' to RTD

Drilling Time: 3900' to RTD

Electric Logs: DIL/CDL//BHCS/CNL

Drillstem Tests: One

Problems: None

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 11 2010

CONSERVATION DIVISION
WICHITA, KS

Formation Tops

Turner 1-12

Heebner	3356'-2014
Toronto	3368'-2026
Kansas City	3987'-2645
BKC	4242'-2900
Marmaton	4301'-2959
Mississippi	4633'-3291
Viola	5069'-3727
Simpson Sd	5119'-3777
Arbuckle	5322'-3980

DST 1: Mississippi

Interval (4637'-4656') Anchor Length 19'

I.F BOB 17 Min	IF 48-56#
I.S.I No Blow	ISI 1652#
F.F BOB 15 Sec	FF 48-76#
F.S.I No Blow	FSI 1405#

Recovery:

60' WMOCG	40%gas	30%oil	10%w	20%mud
60' GOCM	4%gas	15%oil	%w	81%mud
15' GM	2%gas	%oil	%w	98%mud

Summary: Due to structural position and log information, the decision was made to case the Turner 1-12 for further evaluation

Respectfully Submitted,
James F Dilts

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 11 2010

CONSERVATION DIVISION
WICHITA, KS