

Geological Report

American Warrior Inc.
Walker #1-23
410' FNL & 980' FEL
Sec. 23 T34S R7W
Harper County, Kansas

James Dilts
Geologist

American Warrior, Inc.

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 09 2010
CONSERVATION DIVISION
WICHITA, KS

General Data

Well Data: American Warrior Inc.
Walker #1-23
SE-NW-NE-NE
410' FNL & 980' FEL
Sec. 23 T.34S R.7 W.
Harper County, Kansas
API # 15-077-21, 619-0000
Lat N 37 04 42.924354
Long W 98 02 30.09872

Drilling Contractor: Val Drilling Co.

Spud Date: 3/10/2008

Rotary TD Date: 3/23/2008

Rotary TD: 5176'

Elevation: 1356' Ground Level
1366' Kelly Bushing

Casing: Surface 321' 8 5/8" 24# surface casing set at
331' w/225 sx 60/40 3%cc 2%gel
Production 5177' 5.5" 17# at 5188'w/

Samples: 10' wet and dry, 2700' to RTD

Drilling Time: 2700' to RTD

Electric Logs: DIL/CDL//BHCS/CNL

Drillstem Tests: Two

Problems: None

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 09 2010

CONSERVATION DIVISION
WICHITA, KS

Formation Tops

Walker 1-23

Heebner	3390'-2024
Toronto	3410'-2044
Brown Lime	3762'-2296
Kansas City	4016'-2650
Marmaton	4338'-2972
Pawnee	4423'-3057
Ft Scott	4462'-3096
Cherokee	4471'-3105
Mississippi	4653'-3287

DST 1: Mississippi

Interval (4657'-4671') Anchor Length 14'

I.F Strong Blow BOB 5 Sec	IF 52-73#
I.S.I No Blow	ISI 1858#
F.F Strong Blow BOB Imm	FF 90-66#
F.S.I No Blow	FSI 1815#

Recovery: 4639' GIP

DST 2: Viola

Interval (5065'-5100') Anchor Length 35'

I.F Strong Blow BOB 13 Min	IF 84-67#
I.S.I No Blow	ISI 264#
F. F Weak Blow 3" Died Off	FF 42-111#
F.S.I No Blow	FSI 167#

Summary: Due to structural position and log information, the decision was made to plug and abandon the Walker 1-23

Respectfully Submitted,
James F Dilts

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 09 2010

CONSERVATION DIVISION
WICHITA, KS