

FARM CHARLIE CARR

NO. 1

23-34-7W
 COUNTY Harper

TOTAL DEPTH 5155


COMM. 3-28-67

COMP. 4-20-67

SHOT OR TREATED

CONTRACTOR Corbett Drlg.

ISSUED 6-10-67



CASING

20	10	
15	8 5/8"	@ 260' w/175 SX
12	6	
13	5	

ELEVATION 1355' KB

PRODUCTION DRY/SIMP

FIGURES INDICATE BOTTOM OF FORMATIONS

FROM	TO	FORMATION	
0	262	Surface clay & red beds. Drilled 12 1/2" hole, set 8-5/8" 28# casing @ 260' and cemented with 175 sax reg., 3% c.c. & 2% gel.	
262	1577	Shale and anhydrite.	(Slope test 1 deg. @ 1577')
1577	1725	Lime & Shale.	
1725	1871	Shale, lime & sand. (Sand, 1742-65)	
1871	2927	Shale & lime.	
2927	3052	Shale/w/ sandy lime & lime streaks.	(Slope test 3/4% @ 3052')
3052	3160	Shale & lime.	
3160	3320	Lime, shale & sand.	
3320	3396	Shale & lime.	
3396	3430	Shale, lime & hard sand.	
3430	3805	Shale & lime. (Stalnaker 3796')	
3805	3892	Sand, shale & lime.	(Slope test 3/4 deg. @ 3840')
3892	4025	Shale & lime.	
4025	4065	Kansas City Lime. (Top K.C. 4063')	
4065	4090	Layton sand.	
4090	4319	Shale & lime.	(Slope test 3/4 deg. @ 4259')
4319	4366	Checkerboard lime.	
4366	4544	Marmston (Big Lime/Oswago)	
4544	4570	Cherokee shale.	
4570	4688	Cherokee sand zone.	
4688	4988	Mississippi Lime.	(Slope test 3/4 deg. @ 4740')
4988	5100	Lime & shale.	(Slope test 1/2 deg. @ 5084')
5100	5135	Shale.	
5135	5147	Shale & lime.	
5147	5155	Simpson sand.	
5155	5155	Total depth. Dry & abandoned.	

Pumped heavy rotary mud in hole to 250'; set Howco plug & 25 sack cement plug @ 250'; set Howco Plug & 15 sack cement plug 40' to surfa

TOPS: SCOUT	
Heebner	3390
Stalnaker	3796
Kansas City	4040
Mississippi	4680'
Viola	5106
Simpson Dolomite	5130
Simpson Sand	5142