



Operator \_\_\_\_\_ DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. \_\_\_\_\_ Lease Name \_\_\_\_\_


S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_ E \_\_\_\_\_ W \_\_\_\_\_

**WELL LOG**  
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



\_\_\_\_\_  
Signature

\_\_\_\_\_  
Title

\_\_\_\_\_  
Date

3-34-8W

**McCoy Petroleum Company**

502 UNION CENTER BUILDING

WICHITA, KANSAS 67202

PHONE (316) 265-1841

DAILY REPORT

McCoy Petroleum Company & Petroleum, Inc.  
Halbower "B" No. 1  
SE NE SW Sec. 3-34S-8W  
Harper County, Kansas

Contractor: Sweetman Drilling, Inc. - Rio #1

Elevations: 1367 KB  
1364 DF  
1358 GL

- 2-15-72 Move in Rotary tools: Spud @ 6:00 P.M.
- 2-16-72 Set new 8-5/8" 20# surface casing at 260 feet. Globe cemented with 200 sx common, 2% gel, 3% CC. Plug down @ 1:15 A.M. W.O.C. @ 7:00 A.M.
- 2-17-72 Drilling at 1695'.
- 2-18-72 Drilling at 2420'.
- 2-19-72 Drilling at 3071'.
- 2-20-72 Drilling at 3544'.
- 2-21-72 Drilling at 4088'.
- 2-22-72 Circulating for samples at 4252'.
- 2-23-72 Drilling at 4500'.
- 2-24-72 Logging at 4625' RTD.



McCoy Petroleum Company & Petroleum, Inc.  
Halbower "B" No. 1

3-34-8w



DST #1 4604-4625 (Mississippian)

Open 30", S.I. 45", Open 60", S.I. 90".

Gas to surface in 1-1/2 minutes.

Gauge 490,000 CFG/10" on 1st open,

595,000 CFG/20"

625,000 CFG/30"

Gauge 847,000 CFG/15" on 2nd open,

870,000 CFG/30"

893,000 CFG/45"

893,000 CFG/60"

Recovered 20 feet of gas cut mud.

18HP 1862# FBHP 1850# FP 95-113# 113-131# HH 2543# BHT 124°.

WELEX TOPS


Heebner	3410(-2043)	
Douglas Sand	3465(-2098)	
Iatan	3730(-2363)	
Stalnaker Sand	3761(-2394)	
Kansas City	4033(-2666)	
Stark Shale	4180(-2813)	
Base Kansas City	4267(-2900)	
Cherokee Shale	4452(-3085)	
Mississippian Lime	4598(-3231)	
Porosity Zone	4605(-3239)	
Mississippian Dolomite	4614(-3247)	
LTD	4625(-3258)	(TD reached - 4621)

Set 5-1/2" used, 3500# Tested, 14#, J-55, 8rd production casing 20' off bottom at 4605' Globe cement w/150 sx salt sat. common, 2% gel. Plug down at 2:00 A.M. 2-25-72

2-25-72 W.O.C.

3-34-8W -  
SE NE SW

KANSAS



WELL LOG  
HALBOWER # 41  
SE NE SW 3-34-8W  
Harper County, Kansas

API # 15-077-20141

Name of Operator: McCoy Petroleum Company  
502 Union Center Bldg.  
Wichita, Kansas 67202

Date Completed: February 25, 1972

<u>FROM</u>	<u>TO</u>		LOG TOPS:
0	380	Red bed	HEEB 3410
380	1020	Shale	DOUG SD 3465
1020	3761	Shale and lime	IAT 3730
3761	3861	Sand	STAL SD 3761
3861	4090	Shale and lime	KC 4033
4090	4625	Lime	STARK 4180
4625		Total Depth	BKC 4267
			CHER SH 4452
			MISS LM 4598
			MISS DOL 4614
			LTD 4625
			RTD 4625

L

STATE OF KANSAS

COUNTY OF BARTON ss

Gary L. Hawk, Secretary of Sweetman Drilling, Inc., being first duly sworn on oath says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.

Gary L. Hawk  
Gary L. Hawk

Subscribed and sworn before me this 25th day of February, 1972.

Mary Ann Schwamborn  
Notary Public Barton County

My Commission Expires 7-10-73

FILED  
FEB 27 1972  
BARTON COUNTY