

ANSAS DRILLERS LOG

IMPORTANT
Kans. Geo. Survey request
samples on this well.

15-077-20548

API No. 15 — 077 — 20,548
County Number

Operator

~~Wichita Drilling Co.~~

J. A. Mull, Jr.

Address

Main 221, Suite 300 Wichita, Kansas 67202

Well No.

#1

Lease Name

Kaup

Footage Location

660 feet from (N) 1/4 line

660 feet from (E) 1/4 line

Principal Contractor

Blue Goose Drlg.

Geologist

Doug McGinness

Spud Date

10-22-79

Total Depth

4700

P.B.T.D.

Date Completed

10-31-79


Oil Purchaser

S. 14 T. 34 R. 9 W

Loc. NE SW

County Harper

640 Acres
N



Locate well correctly

Elev.: Gr. 1299

DF KB 1306

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	20#	249	Common	200	3% cc 2% Gel
Surface Sand & Shale		250					
Shale & Sand		1449					
Anhydrite		1453					
Shale & Sand		1995					
Lime		2205					
Shale & Sand		2477					
Shale & Lime		2785					
Shale & Shells		3050					
Shale & Sand		3315					
Shale & Lime		4670 TD					
					Sample:		
					Heebner	3465	
					Kansas City	4060	
					Stark	4208	
					B/KC	4291	
					Cherokee	4465	
					Miss	4576	
					RTD	4700	

J. A. MULL, JR.

MAIN 221

#1 KAUP

14-34-9W

C NE SW


WICHITA, KS. 67202

CONTR BLUE GOOSE DRLG., INC. CTY HARPER

GEOL DOUG MC GINNESS

FIELD HIBBORD EXT (1/4 N)

E 1306 KB CM 10/22/79 CARD ISSUED 11/15/79 IP D&A/MISS 10/31/79



API 15-077-20,548

SMP	TOPS	DEPTH	DATUM
HEEB		3465	-2159
KC		4060	-2754
STK		4208	-2902
BKC		4291	-2985
CHER		4465	-3159
MISS		4576	-3270
RTD		4700	-3394

8-5/8" 249/200sx

NO LOG

DST (1) 4580-4615/30-30-120-90, REC 190' M, NS, SIP 406-1859#, FP 142-142/142-142#

DST (2) 4620-4640/30-30-90-60, REC 660' GIP, 65' OCM, SIP 162-304#, FP 40-40/60-60#

DST (3) 4640-4670/30-30-90-60, REC 10' M, 180' HGC&SL OCM, SIP 906-447#, FP NONE/142-142#