

SCOUT TICKET

COUNTY	Clark	STATE	Kansas	DATE	4/30
COMPANY	United Producing et al (Ashland Ref. & Sunray)				
FARM	J. C. Harper	NO.	1		
SEC.	9	TWP.	34	RGE.	21
Location in Sec.				ELEV.	1894 DF
Fr. N.	Fr. S.				1887 gr.
Fr. E.	Fr. W.				1899 DF
C	NW	SE			
			MISS. TEST		

PERFORATIONS	GAS PAYS	CASING RECORD
<i>Schl</i>	Hollenberg	23" 115 (200)
<i>Heebner 4311</i>	Herington	15 3/8 505 (500)
<i>Lans 4545</i>	Paddock	8 5/8 2375 (350)
<i>Marm. 5124</i>	Krider	7"
<i>Cherokee - 5286</i>	Odel	6"
<i>Chet 5578</i>	Winfield	5 1/2 5565 (300)
<i>Sx Lan 5548</i>	Gage	TD 556p
<i>Morrow Sh. 5428</i>	U. Ft. Riley	PB
	L. Ft. Riley	Nat
	<i>Heebner 4311</i>	Acid
	<i>Lans 4547</i>	AA
	<i>Marm 5155</i>	DEL
	<i>Morrow 5445 CT</i>	Rock
Contractor	Parker	

4/28/53 RURT

MAY 5 1953 Ø 1520 MAY 12 1953 Ø 2782 MAY 19 1953 Ø 4612
MAY 25 1953 D.S.T #1 4813-26 open 30 min. rec 92'
salty mud. T.P.O. B.H.P. 1875-P (15)
Ø 4860 JUN 2 1953
C #1-5450-80 - 27 1/2
19 1/2 sand, sh. to good odor
8' sh.
D.S.T 5447-81 open 50 min. gas in 2 1/2 min
rec 5' g.c. m. 76 225-P - 480-P B.H.P. 7980 (30)
max gauge 1484 A.
C #2 5481-5502 rec 20'
8' B, tan, hbl. lower bottom 2' grayish
green
1" sh. grayish green
7' B, dk green, some sh. fossils
w/ green sh. laminations
4' sh. green. V. lgy hbl.

35.16
18.79
36.39
55

$$\begin{array}{r} 5428 \\ 1579 \overline{) 8428} \\ \underline{7639} \\ 789 \end{array}$$
$$\begin{array}{r} 5516 \\ 1819 \\ \hline 2639 \\ 1355 \end{array}$$

550719 rec 2 1/2' to +5' ch.
5519-36 rec 17'
7' to +10' ch.

T.D. 5566

JUN 9 1953

Jet (20) 5443-48 Jet (40) 5459-69
2' 26" w/ PWC @ 5440: open 2 1/2 hrs - 600 MCT.
Pulled 26y.

Jet (20) 5432-43 Jet (50) 5458-59
2' 26" w/ PWC @ 5440: 11 M.B.D 1002 M
A/200 (bowl) - 1500 M

JUN 16 1953

JUN 23 1953

7/1500 gal - 8000 M 1" chokes 7 T.P. 350 M
6000 M 2 3/4" - 7 T.P. 950 M

Back Pressure Test

3/4" choke 7650 M + 8.2 bbls fluid per M
7 T.P. 524 M

Calc D.F. 14000 M
96 hr SIT.P. 1681 M

Ⓟ