

10-35-1W

Total Depth. 4511'

Comm. 4-28-58

Comp. 5-16-58


Shot or Treated.

Contractor. Harold Martin Drilg.

Issued. 8-16-58

County Sumner

KANSAS



CASING:

8 5/8" 343' cem w/250 sx.

5 1/2" 3376' cem w/80 sx.

Elevation. 1130' RB

Production. 15 BOPD

Figures Indicate Bottom of Formations.

shale & sand	25	lime grey	4068
shale & brkn. lime	30	Miss. lime (grey)	4088
brkn. lime & shale	50	Miss. lime (brwn & grey)	4116
lime & shale	70	Miss. lime & chert	4120
brkn lime & shale	230	chat & chert	4158
shale & shells	250	Miss. lime (white)	4173
lime & shale strks	305	Miss. lime (grey, white)	
shale & lime	333	& chert	4197
lime	345	lime Miss.	4227
lime & shale strks	520	lime	4267
sandy shale & lime strks	650	grey lime & dolomite	4293
shale & lime	675	shale & lime	4339
lime & shale	830	Chattanooga shale &	
sand	860	lime	4367
lime & shale	915	sand Simpson	4387
shale	935	sand & shale	4401
lime & sandy lime	1000	Simpson sand	4410
lime & shale strks	1245	shale & sand	4430
lime & shale strks	1260	sand & shale	4463
sandy lime & shale	1350	sand	4477
sandy shale & lime strks	1460	sand & shale	4509
lime & shale	1510	Arbuckle	4511
sandy shale & lime strks	1520	Total Depth	
shale & limey shale	1640		
lime & shale	1765	TOPS: SCOUT	
shale & lime strks	1985	Stalnaker	2840
shale & lime strks	2045	Layton	3244
lime & shale	2145	Kansas City	3430
lime & shale strks	2200	Mississippi	3941
lime & shale	2525	Simpson	4367
sand (hard)	2535	Arbuckle	4502
lime & shale	2603		
sand & shale	2635		
shale & lime	2790		
shale & lime strks	2836		
shale & sand	2995		
shale	3012		
shale & sand	3070		
shale & lime	3230	lime-Oswego zone	3765
shale & sandy shale	3244	lime & shale	3820
Layton	3255	shale & lime	3905
sand Layton	3350	sand & shale	3921
shale	3385	shale & lime	3941
shale & sand strks	3430	lime	3948
lime & black shale	3449	Miss. lime & shale	3982
lime (K.C. zone)	3471	Miss. chat & chert	4015
lime (K.C.)	3536	Miss. lime	4031
lime & shale	3550	Miss. lime (white)	4042
shale & lime	3621		
Oswego lime	3648		