

KANSAS DRILLERS LOG


S. 6 T. 35 R. 11 ~~XX~~ W

API No. 15 — 007 — 20,876 ✓
County Number

Loc. SW SW SE

County BARBER

640 Acres
N



Locate well correctly

Elev.: Gr. 1383

DF 1389 KB 1393

Operator
Molz Oil Co.

Address
RR 2, Kiowa, KS 67070

Well No. 1 Lease Name Eloise

Footage Location
360 feet from (S) line 2470 feet from (E) line

Principal Contractor Sweetman Drilling, Inc. Geologist Gordon W. Keen

Spud Date 1-18-80 Total Depth 4900 P.B.T.D.

Date Completed 3-17-80 Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	14 3/4"	8 5/8"		991	Common	500	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at
2 3/8"	4840	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1500 Gal. 15% Demud	
600,000 SCF Nitrogen	

INITIAL PRODUCTION

Date of first production 3-17-80 Producing method (flowing, pumping, gas lift, etc.) Pumping

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	26 bbls.	500,000 MCF	50 bbls.	CFPB

Disposition of gas (vented, used on lease or sold) Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

MOLZ OIL COMPANY

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No.

1

Lease Name

Eloise

S 6 T 35 R 11 W

30' N & 160' W of C-SW/4 SW/4 SE/4

WELL LOG


Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Shale Black Carb	3801	3820	Heebner	3801
Limestone	4335	4732	Kansas City	4335
Shale & Limestones	4732	4807	Cherokee Fm	4732
Limestone & Chert	4807	4900TD	Mississippi	4807
DST #1 Miss. Misrun				
DST #2 4808-16				
Wk to Strng blo				
Rec. 15' SOCM				
IF 52-46/30"				
ISIP 208#/60"				
FF 52-52/60"				
FSIP 291#/90"				
IH 2617" FH 2502#				
DST #3 4816-27				
Wk to Strong Blow				
Rec 15' OCM				
4 stds GIP				
IF 52-41/30"				
ISIP 145#/60"				
FF 52-52/60"				
FSIP 187#/120"				
IHP 2554# FHP 2502#				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received



Signature

Title

13-22-80

Date

0-32-111