

State Geological Survey
KANSAS DRILLERS LOG

IMPORTANT
Kans. Geo. Survey request
samples on this well.

6-35-11W ✓

API No. 15 — 007 — 20,324
County Number

Operator

Molz Oil Company

Address

R. R. #2 Kiowa, Kansas 67070

Well No.

#A-1

Lease Name

Rathgeber

Footage Location

520

feet from (N) line

660

feet from (W) line

Principal Contractor

Sweetman Drlg.

Geologist

Douglas H. McGinness

Spud Date

5-28-75

Total Depth

5143

P.B.T.D.

-

Date Completed

12-10-75 (State Test)

Oil Purchaser


Permian

S. 6 T. 35 R. 11 W

Loc. N2 NW SW

County Barber

640 Acres



Locate well correctly

Elev.: Gr. 1390

DF 1397 KB 1400

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/2	103/4	20	240	common	200	regular add. 3%cc 2% Gel
Oil String	7 7/8	5 1/2	15	5132 1/2	common	175	"

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type d.p.	Depth interval
			4		5129-5132
TUBING RECORD					
Size 2 3/8	Setting depth 5096	Packer set at Hung			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
none	

INITIAL PRODUCTION

Date of first production 7-23-75 (temporary)	Producing method (flowing, pumping, gas lift, etc.) flowing
RATE OF PRODUCTION PER 24 HOURS 34 bbls.	Gas 40 MCF Water none Gas-oil ratio approx 1x1 CFPB
Disposition of gas (vented, used on lease or sold) vented	Producing interval (s) 5129-5143

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Molz Oil Company

Oil

Well No.

Lease Name

#1-A

Rathgeber

S 6 T 35S R 11W E
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
			Kansas City	4350
			Mississippi	4784
DST #1 Open 2 hr., G/35", F/12 MCFG Recovered 70' O&GCM, 120' HO&GCM, BHP #1253/30" FP #51-81 & FBHP #1655/60"	4790	4810		
DST #2 Open 2 hr., Recovered 90' O&GCM, 120' O&GCMW, 120' VSO&GCMW, BHP #1394/30" FP #61-156, FBHP #1478/60"	4822	4857		
			Kinderhook	5030
			Chattanooga	5104
			Misener	5128
DST #3 Open 1 1/2 hr., G/5", F/326 MCFG/5", Decreased to 68MCFG/60", Flow spray of oil/60", reversed out oil, recovered 300' Muddy oil below circulating sub, BHP #2000/30" FP 249-665, FBHP #2010/60" 42 gravity @ 60	5123	5135		
			Maquoketa Sh.	5132
			Total Depth	5143

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received



Molz Oil Co

Signature

J. H. Smith

Title

Date

12-19-75

WELL LOG
Rathgeber A#1
N/2 NW SW 6-35S-11W
Barber County, Kansas

6-35-11w

15-007-20324

Name of Operator: Molz Oil Company
Route #2
Kiowa, Kansas 67070

Date Completed: June 10, 1975

<u>FROM</u>	<u>TO</u>	
0	15	Sand
15	870	Red Bed and shale
870	1165	Anhy. and shale
165	3703	Shale and lime
3703	3716	Sand
3716	4447	Lime and shale
4447	4753	Lime
4753	4790	Lime and sand
790	5124	Miss. lime
5124	5135	Misner sand
5135		Total Depth

STATE OF KANSAS

COUNTY OF BARTON ss



Gary L. Hawk, Secretary of Sweetman Drilling, Inc., being first duly sworn on oath says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.

Gary L. Hawk
Gary L. Hawk

Subscribed and sworn before me this 19th day of June, 1975.

Nancy Ann Schwaborn
Notary Public Barton County

My Commission Expires 7-10-77



RECEIVED
STATE CORPORATION COMMISSION

JUN 20 1975

CONSERVATION DIVISION
Wichita, Kansas