

WICHITA BRANCH
WELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 007 — 20,820
County Number

Operator

McGinness Oil Co.

Address

920 Woodrow Wichita, Kansas 67203

Well No.

#B-1

Lease Name

Lohmann

Footage Location

660

feet from (N) (S) line

400

feet from (E) (W) line

Principal Contractor

Union Drilling Co. Inc.

Geologist

Douglas H. McGinness

Spud Date

10-26-79

Date Completed

1-8-80

Total Depth

4875

P.B.T.D.

4832

Directional Deviation

Oil and/or Gas Purchaser


Lawson Purchasing Kiowa, Ks

S. 3 T. 35 R. 12 W

Loc. W2 SW NW

County Barber

640 Acres



Elev.: Gr.

DF KB 1446

CASING RECORD

Report of oil strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 $\frac{1}{2}$	8 5/8"	28	n 307	common	250	2% gel 3%cacl
Production	7 7/8"	4 $\frac{1}{2}$	10 $\frac{1}{2}$	4874	common	150	2% gel 3%cacl

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type dp's	Depth interval
			4/ft	3 1/8	4824-30
TUBING RECORD					
Size	Setting depth	Packer set at			
2 3/8"	4788' hung in	braden head			


ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 GA (15%) demud & Foam Frac (#21,000SD 20-40 mesh - 574,300	SCF(N ₂) 4824-30

INITIAL PRODUCTION

Date of first production 1-8-80		Producing method (flowing, pumping, gas lift, etc.) pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil 75	Gas	Water 25	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator McGinness Oil Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY, HOLE, SWDW, ETC.: Oil Oil															
Well No. B-1	Lease Name Lohmann																
S <u>3</u> T <u>35</u> R <u>12</u> W <u>E</u>																	
WELL LOG <small>Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.</small>		<small>SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.</small>															
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 60%; text-align: left;">NAME</th> <th style="width: 40%; text-align: left;">DEPTH</th> </tr> </thead> <tbody> <tr> <td>Kansas City</td> <td>4375 (-2929)</td> </tr> <tr> <td>B/KC</td> <td>4622 (-3176)</td> </tr> <tr> <td>Cherokee</td> <td>4757 (-3311)</td> </tr> <tr> <td>" Sand</td> <td>4784 (-3338)</td> </tr> <tr> <td>Mississippi</td> <td>4805 (-3359)</td> </tr> <tr> <td>Total Depth</td> <td>4875 (-3429)</td> </tr> </tbody> </table>	NAME	DEPTH	Kansas City	4375 (-2929)	B/KC	4622 (-3176)	Cherokee	4757 (-3311)	" Sand	4784 (-3338)	Mississippi	4805 (-3359)	Total Depth	4875 (-3429)
NAME	DEPTH																
Kansas City	4375 (-2929)																
B/KC	4622 (-3176)																
Cherokee	4757 (-3311)																
" Sand	4784 (-3338)																
Mississippi	4805 (-3359)																
Total Depth	4875 (-3429)																
<div style="margin-bottom: 20px;"> DST #1 4780-98 30-30-60-60 50' Oil Specked Mud, 30' SOCM, #126-63-73-#275 </div> <div> DST #2 4819-34 30-30-120-90 GTS 145" TSTM, 300' HO&GCM, #1123-73-137-#1731. </div>																	
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.																	
Date Received	<div style="text-align: center;">  Signature McGinness Oil Company President Title 1-25-80 Date </div>																