


3-35-12W

State Geological Survey
KANSAS DRILLERS LOG
WICHITA, BRANCH

IMPORTANT
Kans. Geo. Survey request
samples on this well.

S. 3 T. 35 R. 12
Loc. C SE NE
County Barber



Locate well correctly
Elev.: Gr. 1425
DF 1432 KB 1435

API No. 15 — 007 — 20,391
County Number

Operator
Molz Oil Company

Address
Route #2 Kiowa, Kansas 67070

Well No. #1 Lease Name Lohmann

Footage Location
1980 feet from (N) line 660 feet from (E) line

Principal Contractor Sweetman Drlg. Geologist Douglas H. McGinness

Spud Date 2-9-76 Total Depth 5200 P.B.T.D.

Date Completed 2-21-76 Oil Purchaser none

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface	15"	10 3/4	20	293	Portland	250 sx	2% gel, 3% cc

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
MOLZ OIL COMPANY

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
D & A

Well No. 1 Lease Name Lohmann

S 3 T 35S R 12 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.
DRESSER ATLAS Log Tops

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<p>DST #1 4750-4840 Op. 1½ hr., Recovered 540' GIP, 135' GCM #221/30-100-130-#261/60"</p> <p>DST #2 5156-74 Op. 1½ hr., Recovered 45' GCMW (trace Oil) 180' GCMW 675' WATER #2023/30"-60-481-#2033/60"</p>			Elgin Sd	3677 (2242
			Heebner	3840 (-2405
			Stalnaker SD	4140 (-2705
			Kansas City	4378 (-2943
			Cherokee	4751 (-3316
			" sd	4782 (-3347
			Mississippi	4794 (-3359
			Kinderhook	5068 (-3633
			Misener Sd	5169 (-3734
			Maquoketa	5180 (-3745
		TD	5200 (-3765	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



Signature _____
Title _____
Date 2-28-76