

41-35-12W

API No. 15 — 007 — 20872
County Number

Operator

Beren Corporation

Address

970 Fourth Financial Center, Wichita, Kansas 67202

Well No.

6

Lease Name

BLACKSTOCK

Footage Location

feet from (N) (S) line

feet from (E) (W) line

Principal Contractor

Geologist

BEREDCO

Spud Date

May 21, 1980

Date Completed

May 31, 1980

Total Depth

5237

P.B.T.D.

Directional Deviation

Oil and/or Gas Purchaser

Elev.: Gr.

1452

DF _____

KB 1465

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8-5/8	28#	403	60-40 pozmix	300	2% gel, 3% CC
Production		5½	14#	5237	60-40 pozmix	300	

RB	0	403
RB and shale	403	1790
Shale and lime	1790	2890
Shale	2890	3100
Shale and lime	3100	4820
Miss	4820	4931
Shale and lime	4931	5237
RTD	5237	

BEREN CORPORATION
970 FOURTH FINANCIAL CENTER #6 BLACKSTOCK C S/2 NW NW
WICHITA, KS 67202
CONTR BEREDCO CTV BARBER
GEOL BILL IVERSEN FIELD HARDTNER
E 1465 KB CM 5/20/80 CARD ISSUED 8/21/80 IP OIL WELL
1452 GL MISS-INTV NA
15-007-20,872

[illegible]

8-5/8" 403/300sx, SET 5 $\frac{1}{2}$ "

DST (1) 4774-4790 (CHER SD)/30-30-30-30,
REC 51M, SIP 42-52#, FP 42-42/
52-52#

52-52#
DST (2) 4776-4820 (MISS)/45-45-120-90,
GTS 11" GA 126 MCF DECR TO 45 MCF
REC 50' HOGCM, 650' CL 0, SIP
1741-1731#, FP 116-126-243#
DST (3) 5117-5237 (MISN SD)/45-45-60-
90, REC 100'M, SIP 118-162#, FP
75-86/108-118#

75-86/108-118#
MICT - CO, TSTD - COMP AS (MISS) OIL
WELL - POTENTIAL & INTV NA - NO OTHER
INFO TO BE RELEASED AT PRESENT - WILL
RELEASE INFO WHEN AVAILABLE

INDEPENDENT OIL & GAS SERVICE