

WICHITA BRANCH
KANSAS DRILLERS LOG

API No. 15 — 007 — 20704
County Number

Operator
Damson Oil Corporation

Address
3033 NW 63, Suite 150-E, Oklahoma City, Ok 73116

Well No. 1 Lease Name Billy Max Graves

Footage Location
330 feet from (N) (S) line 315 feet from (E) (W) line

Principal Contractor Damac Drilling Geologist Ed Grieves

Spud Date 1-25-79 Total Depth 4873' P.B.T.D. 4867'


Date Completed 2-14-79 Oil Purchaser The Crude Company

S. 7 T. 35S R. 12 X

Loc. 15' E of C SE SE

County Barber

640 Acres



Elev.: Gr. 1394'

DF 1403 KB 1405

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/2"	8 5/8"	20	280'	Class "H"	175	3% CaCl ₂ 2% Gel
Production	7 7/8"	4 1/2"	10.5	4872'	Class "H"	150	10% Salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	1 11/16 Biwire	4819' - 4826'

TUBING RECORD

Size	Setting depth	Packer set at
2 3/8"	4813'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized w/1000 Gal. clean-up acid	4819' to 4826'
Fraced w/2000 Gal. 70 quality foam & 20,000# 20-40 Sand	4819' to 4826'

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
2-27-79	Pumping

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	90 bbls.	TSTM	MCF 30 bbls.	CFPB

Disposition of gas (vented, used on lease or sold) Producing interval (s)
Mississippi Chat 4819' to 4826'

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Damson Oil Corporation

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. 1	Lease Name Billy Max Graves	Oil
---------------	--------------------------------	-----

S 7 T35S R12 ~~X~~ W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Shale w/interbedded sandstones	0	1220		
Anhydrite	1220	1870		
Interbedded shale & sandstone	1870	3160		
Sandstone	3160	3240		
Shale	3240	3670		
Sandstone	3670	3760		
Shale	3760	3860	Heebner	3825
Limestone	3860	3900		
Shale	3900	4180		
Sand	4180	4240	Tonkawa Sd.	4180
Shale	4240	4354	Lansing/KC	4354
Limestones w/interbedded shales	4354	4738	Cherokee Sh	4738
Shale	4738	4763	Cherokee Sd	4763
Sand	4763	4775		
Shale	4775	4811	Mississippi	4811
Lime	4811	4873	LTD	4873

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<i>Stan DeLong</i> Signature
	Engineer Title
	March 29, 1979 Date

92-1500